

Bill Of Quantities: Removal and replacement of DN 900 Valves - Pumpsets 9 & 20 including auxiliary DN 150 Bypass valves

Pricing Schedule.

	MILESTONES / LINE ITEMS	Estimated delivery period (where applicable)	UNIT PRICE (where applicable)	QUANTITY (where applicable)	COSTING
1.	Remove and install 1x DN900 Delivery Gate Valve (9Tons) x70 Bar as issued with bolting ancillaries			1	
2.	Fabricate Valve 2x Stubs for DN900 Valve (6Tons) x70 Bar, using free issued Materials			2	
3.	PS 09 Remove & install DN 900x70 Bar Valve Rig including DN150 Bypass			1	
4.	Provide a 50-Ton Mobile Crane for 44 hours. There must be a reliever to the crane operator and his assistant if needed			1	
5.	Galvanic Corrosion & sealant Material for the valves to be installed (6xDN 900x & 2x DN200 Klinger Type 4438 Steel reinforced) FULLFACE			1 Set	
6.	Documentation: NDT all welding runs by dye penetrant and magnetic particle test and submit a Data Book for related to all welding work in line with QCP+ Safety file			1	
TOTAL					
VAT					
TOTAL [VAT INCLUDED]					