

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Project Name: Major and Minor Distribution projects

Project Address: Gemma Gluster: NWOU

Scope of the project: Provision of Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators within Distribution Gemma Cluster-North-West on an “as and when” required basis over a period of four (4) years

Compiled by	Accepted by	Accepted by
Name : Tshidi Suping	Name : Magda Wyngaardt	Name : Solly Mathe
Signature :	Signature : 	Signature :
Date : 08/04/2026	Date : 22.05.2026	Date :
Contractor Safety Officer North West / Gemma Cluster	Contractor Safety Manager Northern Cape/ Gemma Cluster	Project Manager North West/ Gemma Cluster

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Content

	Page
1. Introduction.....	7
2. Supporting Clauses.....	7
2.1 Scope	7
2.1.1 Purpose.....	8
2.1.2 Applicability	8
2.2 Normative/Informative References	8
2.2.1 Normative	8
2.2.2 Informative.....	9
2.4 Abbreviations.....	13
2.5 Roles and Responsibilities	14
2.6 Related/Supporting Documents	25
3. Specification.....	25
3.1 Scope of work.....	25
3.2 Legal Compliance	28
3.2.1 Section 37(2) (Legal) Agreement.....	28
3.2.2 Hazardous work by children (Child Labour).....	28
3.3 Eskom Requirements	29
3.4 Construction Professional Registration.....	30
3.5 Notification of Construction Work	30
3.6 OHS Policy	30
3.7 COID.....	31
3.8 Costing for OHS within the Project.....	31

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.9	Statutory Appointments	31
3.10	Eskom Life-saving Rules.....	32
3.11	Substance Abuse	34
3.12	Contractor organisational Structure.....	34
3.12.1	Principal Contractor Organogram.....	34
3.12.2	Appointed Contractor/s Organogram	35
3.13	Risk assessment (refer to 32-520).....	35
3.14	Safe work procedures / method statements.....	38
3.15	Construction Sites	39
3.16	Fire Equipment and maintenance.....	39
3.17	Flammable and Combustible Liquids	40
3.18.1	Refuelling at the construction site.....	40
3.18	First Aid and Equipment	41
3.19.1	Boxes and equipment.....	41
3.19	OHS Communication Systems.....	42
3.20.1	Statutory Health and Safety Committees	42
3.20.2	Non-statutory health and safety committees	43
3.20.3	Agenda.....	44
3.20.4	Minutes and action items for all health and safety committee meetings	45
3.20.5	Tool box talks / Daily team talks / pre job meetings	46
3.20	OHS Training	46
3.21.1	Induction training	46
3.21.2	Site specific induction training	47
3.21.3	Visitors to site induction	47
3.21.4	General training	47

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.21	Contractor Site Establishment.....	48
3.22.1	Site roads	48
3.22.2	Construction vehicle safety.....	48
3.22	Housekeeping and Order	49
3.23.1	Stacking.....	50
3.23	Workplace Signage and Colour Coding.....	50
3.24	Tools and Equipment.....	51
3.25.1	Hand tools	51
3.25	Ladders	52
3.26	Auditing	53
3.28.1	Approval and compliance of principal contractor OHS plan	53
3.28.2	Eskom OHS audits.....	53
3.28.3	Contractor audits.....	53
3.27	Smoking	53
3.28	Cellular Phones	54
3.29	Occupational Health, Hygiene and Rehabilitation.....	54
3.31.1	Medicals.....	54
3.30	Working at Heights.....	54
3.32.1	General Requirements	54
3.31	Risk Assessments	56
3.32	Safe Work Procedures and Practices / Safe Operating	56
3.33	Personal Protective Equipment Requirements.....	56
3.34	Incident Investigation	57
3.35	Emergency Management.....	58
3.36	Non-Conformance and Compliance	59

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.37	OHS File	60
3.38	Work Stoppage	61
3.39	Hours of Work	61
3.41.1	Normal work	61
3.41.2	Night work	61
3.41.3	Overtime	62
3.40	Omissions from Safety and Health Requirements Specification	62
3.41	4	62
3.42	Project Statistics	62
3.43	Weather Extremes.....	63
3.44	Dismantling, Assembly and Erecting of Structures	63
3.45	Excavation Work.....	65
3.	Revisions	68
6.	Annexures.....	75
6.1	Annexure 1 – Flash Report Template.....	75
6.2	Annexure 2 – Technical Instruction for Transportation of Personnel.....	78
6.3	Annexure 3 – Training Needs Analysis.....	79
6.5	Annexure 4 – Construction Evaluation Template.....	81
6.6	Annexure 5 – 37(2) Agreement Template	99
6.7	Annexure 6 – CR5(1)(K) Appointment Template	102
6.8	Annexure 7 – Acknowledgement Form for Eskom OHS Rules	104
6.9	Annexure 8 – Behavioural Observation Form.....	106
6.10	Annexure 9 – Annexure D OHS Post-contract Reviews	107
6.11	Annexure 10 – Task Observation Form.....	113
6.12	Annexure 11 – Contractor OHS File Hand Back Record	117

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

6.13 Annexure 12 – OHS Tender Evaluation Template..... 120

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

1. Introduction

Eskom's responsibility and commitment is to ensure a safe working environment is in line with its Safety, Health, Environmental and Quality Policy, along with legislative obligations.

This OHS specification is Eskom the minimum requirements which are required to be met for the specific contract and for the duration of the contract period by contractors and where required, the delivery organisation.

The contractor is expected to develop a OHS plan which meets these requirements as well as all the relevant applicable legislation they conform to.

Eskom in no way assumes the contractor's legal responsibilities. The contractor is and remains accountable for the quality and the execution of his/her health and safety programme for his/her employees and appointed contractor employees.

This OHS specification reflects minimum requirements and should not be construed as all encompassing.

Note 1: All the requirements listed hereunder are in relation to the contract and do not supersede or replace any organizational OHS requirements.

Where requirements listed are already in place, then the organisational requirements must be taken cognisance of and listed in the respective OHS plans. If there are any additional Eskom and or legislative requirements listed in the OHS specification, then these must be addressed.

2. Supporting Clauses

2.1 Scope

This OHS specification lists the legislative and Eskom requirements and where applicable, any requirements pertaining to Local Authorities / Municipal by-laws / Environmental legislation that must be met by the contractor.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2.1.1 Purpose

This document will provide a standardised approach to the compilation of OHS specifications throughout Eskom for contracts, standards and NEC 3 contracts.

2.1.2 Applicability

This OHS specification is applicable to any contracting organisation who intends tendering for the contract.

2.2 Normative/Informative References

Parties using this document shall apply the most recent edition of the documents listed in the following paragraphs.

2.2.1 Normative

- [1] Basic Conditions of Employment Act No 75 of 1997.
- [2] Occupational Health and Safety Act and Regulations No 85 of 1993.
- [3] National Environmental Management Act 107 of 1998.
- [4] National Road Traffic Act 93 of 1996.
- [5] 32-37 Eskom Substance Abuse Procedure.
- [6] 32-136 Contractor Health and Safety Requirements
- [7] 240-62196227 Life- saving Rules
- [8] 32-95 Environmental, Occupational Health and Safety Incident Management Procedure
- [9] 32-727 OHSQ Policy
- [10] 32- 418 Working at Heights Procedure
- [11] 240-62946386 Vehicle and Driver Safety Management Procedure
- [12] 32-520 Risk Assessment procedure
- [13] Plant Safety Regulations.
- [14] Directive: Consolidated COVID-19 Direction on Health and Safety in the Workplace
Published 4 June 2020, Government Gazette 43400, GNR 639

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2.2.2 Informative

- [1] Tobacco Products Control Act 83 of 1993 (Updated 2011.05.19)
- [2] SANS 1186 Symbolic Safety Signs
- [3] Constitution of the Republic of South Africa No 108 of 1996
- [4] DMN 34-110 Operating A Vehicle Mounted Crane
- [5] DMN 34-1981 Excavations.

2.3 Definitions

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Definitions	Explanation
Appointed contractor	Means a contractor appointed by the principal contractor
Baseline risk assessment	(32-520) baseline operational risks refer to the health and safety risks associated with all standard processes and routine activities in the business
Business unit (BU)	(32-296) means any defined unit within the Eskom environment, operating as a business under a particular cost-centre number. In the context of this document and in terms of health and safety, any reference to a BU includes a defined unit within any Eskom division and its subsidiaries
Client	(OHS Act) Eskom representative (Internal – Asset Owner), also referred to as the contract administrator/custodian or agent or project manager (as defined in the contract). He/OHS is the person responsible for ensuring that the works or services are executed in terms of the contract, as well as adherence to legislation pertaining to the contract.
Competent person	(OHS Act) means any person having the knowledge, training, experience, and qualifications, specific to the work or task being performed, provided that, where appropriate, qualifications and training are registered in terms of the South African Qualifications Authority Act, 1995 (Act No. 58 of 1995)
Contractor	(OHS Act) means an employer as defined in section 1 of the Act who performs contracted work and includes principal contractors
Construction work	Any work in connection with <ul style="list-style-type: none"> a. the construction, erection, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure. b. the construction, erection, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system or the moving of earth, clearing of land, the making of excavation, piling or any similar civil engineering structure or type of work.
Consultant	means a person providing professional advice
Controlled disclosure	controlled disclosure to external parties (either enforced by law or discretionary)
Duty of care to the environment	(32-136) anybody who causes or has caused or may cause significant pollution or degradation of the environment must take reasonable measures to prevent such pollution or degradation from occurring, continuing, or recurring. If such harm to the environment is authorised by law or cannot reasonably be avoided or stopped, such person must minimise and rectify such pollution or degradation of the environment

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Definitions	Explanation
Employee	(OHS Act) means, subject to the provisions of subsection (2), any person who is employed by or works for an employer and who receives or is entitled to receive any remuneration or who works under the direction or supervision of an employer or any other person
Employer	(OHS Act) means, subject to the provisions of subsection (2), any person who employs or provides work for any person and remunerates that person or expressly or tacitly undertakes to remunerate him/her, but excludes a TES (ex labour broker) as defined in section 1(1) of the Labour Relations Act 1956 (Act No. 28 of 1956)
Environment	(32-94) means: a. the land, water, and atmosphere of the earth; b. micro-organisms and plant and animal life; and c. any part or combination of (a) and (b) and the interrelationships among and between them, and the physical, chemical, aesthetic, and cultural properties and conditions of the foregoing that influence human health and well-being
Environmental Management plan	A detailed plan of action prepared to ensure that recommendations for enhancing or ensuring positive impacts and limiting or preventing negative environmental impacts are implemented during the life-cycle of a project. This Environmental Management Plan should preferably form part of Eskom's Environmental Management System
Eskom requirements	Eskom requirements flowing from directives, policies, standards, procedures, specifications, work instructions, guidelines, or manuals
Fall protection plan	(OHS Act) means a documented plan of all risks relating to working from an elevated position, considering the nature of work undertaken, and setting out the procedures and methods to be applied in order to eliminate the risk
Hazard	(OHS Act) means a source of, or exposure to, danger
Hazard identification	(OHS Act) means the identification and documenting of existing or expected hazards to the health and safety of persons, which are normally associated with the type of construction work being executed or to be executed
Health and safety file	(OHS Act) means a file or other record in permanent form, containing the information required in relation to the contract.
Health and safety plan	(OHS Act) means a document plan that addresses hazards identified and includes safe work procedures to mitigate, reduce, or control hazards identified

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Definitions	Explanation
Health and safety specification	(OHS Act) means a document specification of all health and safety requirements pertaining to associated to a contract, so as to ensure the health and safety of persons.
Health and safety requirements	means comprehensive health and safety requirements for a contract, project, site, and scope of work. This specification is intended to ensure the health and safety of persons, both workers and the public, and the duty of care to the environment. The health and safety requirements must be specific to each contract, project, site, and scope of work
Lifesaving Rules	(240-62196227) a rule that, if not adhered to, has the potential to cause serious harm to people
Medical Certificate of fitness	(OHS Act) means a certificate valid for one year, issued by an occupational health practitioner, issued in terms of the regulations, whom shall be registered with the Health Professions Council of South Africa
Medical surveillance	(OHS Act) means a planned programme or periodic examination (which may include clinical examinations, biological monitoring, or medical tests) of employees by an occupational health practitioner or, in prescribed cases, by an occupational medicine practitioner
Method statement	(OHS Act) means a written document detailing the key activities to be performed in order to reduce, as reasonably as practicable, the hazards identified in any risk assessment
Organisation	may be defined as a group of individuals (large of small) that is cooperating under the direction of executive leadership in accomplishment of certain common objects
Pre-job meetings	(34-227) means a meeting that is held prior to the commencement of the day's work and that is attended by all the relevant employees associated with the work task
Principal contractor	(In the text of this document) Means an employer, as defined in section 1 of the OHS Act, who intends to tender for or has signed a contract with Eskom for services rendered.
Provincial director	(OHS Act) means the provincial director as defined in Regulation 1 of the General Administrative Regulations under the Act
Responsible Manager	Is a Manager of a department, section or operating/business unit who has been appointed as part of the Eskom delegation of authority process with the aim to assist the applicable 16(2) assigned person in executing his/her duties in terms of the Occupational Health and Safety Act

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Definitions	Explanation
Risk assessment	(OHS Act) means a programme to determine any risk associated with any hazard at a construction site in order to identify the steps needed to be taken to remove, reduce, or control such hazard.
Site	(34-228) means an Eskom department, unit, complex, building, specific project, work site, or the site where agents, clients, principal contractors, contractors, suppliers, vendors, and service providers provide a service to Eskom, directly or indirectly
Service provider	any private person or legal entity that provides any service(s) to Eskom for compensation
Subsidiary	(32-94) an enterprise controlled by another (called the parent) through the ownership of greater than 50% of its voting stock
Supplier	(32-1034) means a natural or legal person who renders a service and may include the following current or potential supplier vendor, contractor, consultant
Task	(34-227) a segment of work that requires a set of specific and distinct actions for its completion
Toolbox talks	(34-227) where the team leader, after conducting pre-task planning, shares all the tasks at hand and discusses task allocation, the identified risks, and the control measures with all his/her team members on site before commencing a specific task and documenting the agreed strategy. (This shall be done to ensure common understanding of the tasks, risks, and control measures required.)
The Act	(OHS Act) means the Occupational Health and Safety Act No. 85 of 1993, as amended, and the Regulations thereto
Visitor	any person visiting a workplace with the knowledge of, or under the supervision of, an employer.

2.4 Abbreviations

Abbreviation	Description
AIA	Approved Inspection Authority
BU	Business Unit
CE	Chief Executive
CNC	(Eskom) Customer Network Centre

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Abbreviation	Description
AIA	Approved Inspection Authority
BU	Business Unit
CE	Chief Executive
CR	Construction Regulations of the OHS Act
COID Act	Compensation for Occupational Injuries and Diseases Act
DMR	Driven Machinery Regulations
DoL	Department of Labour (Inspection and Enforcement services – Provincial office)
EAP	Employee Assistance Program
EP	Emergency Preparedness
ERfW	Environmental Regulations for Workplaces
GAR	General Administrative Regulations
GSR	General Safety Regulations
HCA	Hazardous Chemical Substances
LDV	Light Delivery Vehicle
LoG	(COID) Letter of Good Standing
MSDS	Material Safety Data OHSets
NEMA	National Environmental Management Act
OHS Act	Occupational Health and Safety Act and Regulations, 85 of 1993
SACPCMP	South African Council for the Project & Construction Management Professions
SABS	South African Bureau Standard
SANS	South African National Standard

2.5 Roles and Responsibilities

2.5.1 Commitment

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Visible commitment is essential to providing a safe work environment. Managers, supervisors and employees at all levels must demonstrate their commitment by being proactively involved in the day-to-day operations, in particular the Occupational Health and Safety aspects of any project / contract. Legislation requires that each employee must take reasonable care of themselves and their fellow workers, from management level down to the lowest employee level.

2.5.2 Principal contractors and appointed contractors

Note 1: Most of the roles and responsibilities listed apply to both principal contractors and any appointed contractors. Where some of the listed do not apply to both, then the specific responsibilities will be listed and titled. The contractors shall:

1. Carry out all duties as listed in section 8, 9 and 10, the various other regulations that form part of the OHS Act and Regulation 7 of the Construction Regulations.
2. The principal contractor must notify the provincial director of the Department of Labour in writing of all construction work if it falls within the scope of Regulation 4 of the Construction Regulations (if this has not been arranged and or done by the client/agent);
3. Carry accountability and responsibility for the safety and health of their employees and their appointed contractors within their working area, as contemplated by section 37(2) of the OHS Act;
4. Shall keep a record of all employees including the appointed contractor employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.
5. Ensure that all their appointees are made aware of their accountabilities and responsibilities in terms of their appointment and that they advise and assist these appointees in the execution of their duties.
6. Ensure that the minimum legislative, regulatory and Eskom OHS requirements are complied with on all work sites.
7. Give the Eskom project managers and line managers / responsible managers their full participation and cooperation.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

8. Compile a OHS (health and safety) file where all relevant health and safety records must be kept for each work site.
9. The principal contractor must hand over a consolidated (to include any appointed contractors' files) health and safety file to the Eskom project manager on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.
10. Contractors must hand over a consolidated (to include any appointed contractors' files) health and safety file to the principal contractor on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.
11. The principal contractor must provide the project manager with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company. Similarly, the principal contractor must provide the Eskom project manager with all the valid letters of good standing from their appointed contractors.
12. Contractors must provide the principal contractor with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company.
13. Appoint competent staff to perform the project work and ensure that all employees are trained in the health and safety aspects relating to such work and that the employees understand the hazards associated with all other work being carried out on the project.
14. Ensure that all employees are conversant with all relevant work procedures and that they adhere to such procedures. Similarly (without removing the appointed contractors' responsibilities), ensure that their appointed contractors and their employees are conversant with all relevant work procedures and that they adhere to such procedures.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

15. Co-ordinate the activities of all the appointed contractors in the interests of safety and health;
16. Ensure that potential contractors (whom they intend appointing) submitting tenders have made detailed provision for the cost of safety and health measures throughout the project.
17. Stop his /her employees and any appointed contractors if project work is not in accordance with the health and safety plan or if such work poses a threat to the health and safety of persons or a risk of degradation to the environment.
18. Take reasonable steps to ensure cooperation between all their appointed contractors.
19. Only appoint contractors to do work, if satisfied that the contractor has the necessary competencies and resources to perform the work safely.
20. Appoint full-time competent employees in writing to supervise the performance of all specified work throughout the contract period.

Note 2: No work may commence and or continue without the presence of the appointed project manager or project supervisor during performance of the contracted work.

21. Ensure that the supervisor or manager do not supervise work on any site other than the site for which such supervisor has been appointed for.

Note 3: In determining the number of appointed competent supervisors, the nature and scope of work being performed, shall be taken into consideration.

Note 4: If a sufficient number of competent employee(s) have been appointed to assist the construction supervisor, the construction supervisor may supervise more than one site.

22. Appoint a full time SACPCMP registered safety officer for the projects that are 30 days and more.
23. Appoint a part time SACPCMP registered safety officer for minoretic projects and must visit the site once per week.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

24. Not victimise or dismiss employees, by virtue of the employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements;
25. Follow a process of disciplinary action if any of their employees or their appointed contractor employees have transgressed any of the requirements of the health and safety specification, safety and health plans, site rules or any other requirements.
26. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
27. Before the commencement of any work, conduct risk assessments which shall include public safety. This should be done by a competent person appointed in writing with a view to identify hazardous and potentially hazardous work operations.
28. Ensure that pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task or not.
29. Take prime responsibility for all aspects of environmental management associated with the project activity for which they are responsible.
30. Provide any appointed contractor who is making a bid or is appointed to perform work on Eskom's behalf, with the relevant sections of the documented Eskom's OHS Specification.
31. Principal contractors are required to approve appointed contractor's health and safety plans if they meet all the requirements.
32. Must ensure that an organisation medical surveillance programme for the duration of the contract is in place and maintained.
33. Prior to having pre-employment and periodic medicals fitness examinations conducted, person/man job specifications must be compiled and handed to the occupational health practitioner.
34. Ensure that pre-employment, periodic and exit medicals are carried out on their employees. Medical assessments must be conducted by a registered Occupational

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Health Practitioner. During the pre-employment medical, where employees will be required to work at heights, they will also be required to undergo the required employee physical and psychological fitness examinations.

35. Ensure, prior to the commencement of construction work, that all persons involved in the project work, as well as the appointed contractors, have received a health and safety induction training session. Similarly, ensure that all visitors to site undergo the site's induction training.
36. Ensure, prior to the commencement of construction work or contracted work, that all their employees involved in the project work, as well as the appointed contractors, have received task-specific training.
37. Issue risk-based personal protective equipment (PPE) as a measure of last resort to their employees, inspect such equipment regularly and ensure recipients of PPE are trained in the proper use, care and where necessary, the maintenance of PPE;

Note 5: should the principal contractor or his/her appointed contractors entertain visitors on site, they will be held responsible for the provision and wearing PPE.

38. Erect their own site huts, temporary buildings, storage areas, toilets, fencing, and any other structure as may be required. Any such structures shall be positioned and erected in compliance with any instructions from the Eskom project manager and the relevant site safety and fire prevention requirements;
39. On completion of the work remove all structures erected by them, and where required by law rehabilitate the environment.
40. Where performing work with the environment, ensure that minimal damage is done and that where an Environment Management Plan is in place, then adhere to the plan.
41. Respect the rights of land owners/lessors and the preservation of their registered activities;
42. Must have a substance abuse program which must be in line with the requirements of the OHS Act.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

43. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on the work sites.

Note 6: Eskom will not tolerate the presence of anyone who is or who appears to be under the influence of alcohol or any other intoxicating substance whilst performing work for them or on any work site.

44. Ensure that all equipment and tools used comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these;
45. Ensure that all incidents are reported and investigated timeously by competent incident investigators.
46. Be involved in all of their appointed contractor's investigations.
47. Establish health and safety committees, hold such committee meetings on all sites, and ensure that appointed contractors participate in their health and safety meetings.
48. Chair their own health and safety committee meetings and record such meetings.
49. Appoint sufficient number of health and safety representatives in terms of legislative requirements and ensure that the appointed contractors appoint health and safety representatives for their work sites.
50. When appointing contractors, advise the project manager in writing timeously and obtain his/her approval prior to them commencing work.
51. Shall keep a record of all employees including the appointed contractor's employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.

2.5.3 Construction Managers/ Contract Managers

Note 1: No work may commence and or continue without the appointed supervisor or manager during the performance of the contracted work.

1. Not supervise construction work on any construction site other than the site they have been appointed to supervise.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. Assist the contractor and/or the appointed safety officer in conducting site induction training for new staff and site visitors;
3. Instruct and train all employees under their control on any hazardous and related work procedures, before any work commences and thereafter, at such times as may be determined by a risk assessment;
4. Ensure that the minimum legislative and Eskom OHS requirements are complied with on all work sites;
5. Stop any construction work that is not in accordance with the safety and health plan or if such work poses a threat to the safety and health of persons or a risk of degradation to the environment;
6. Ensure that risk-based personal protective equipment (PPE) has been issued and employees wear/use the PPE as instructed.
7. Inspect such PPE on a regular basis and record the inspections;
8. Ensure that all incidents are reported to the client and are investigated.
9. Be involved in all investigations that occur within their area of responsibility.
10. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor.
11. Ensure that employees under their control are conversant with all relevant work procedures and that they adhere to such procedures;
12. Before the commencement of any work, where possible, assist in the conducting of risk assessments and ensure that appropriate mitigating measures have been considered and implemented.;
13. Ensure that daily or pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task. Ensure that the team are involved in the abovementioned risk assessments;
14. Hold tool box talks at the start of each day/ task to discuss health and safety issues as well as confirming the requirements of the daily risk assessments;
15. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
16. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/OHS is under the influence. Furthermore, report such instances to contract management;
17. Ensure that all equipment and tools used on site comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these.
18. Ensure that they and their contractor managers give clear and unambiguous instructions for the project work, to the employees for whom they are responsible for.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

19. Not victimise their employees by virtue of their employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements (reference – section 26 of the OHS Act).
20. Where any work is performed which involves the environment, ensure that minimal damage is done to the environment and that where an Environment Management Plan is in place, then the plan adhere to the plan.
21. Stop any employee or contractor from performing construction work which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.

2.5.4 Contractor site supervisor or Contract Supervisor

Must:

1. Be competent to perform the required supervisory tasks;
2. Ensure their employees and all appointed contractors comply with the required statutory and Eskom project requirements;
3. Inspect all work done by the Contractors to ensure adherence to Eskom's standards and specifications
4. Conduct follow-up inspections to ensure findings are closed out and preventative action is in place.
5. Monitor contractors for adhere to statutory requirements and safety standards.
6. Monitor contractors overall OHS performance on site in order to achieve excellent results
7. Ensuring a Safe working environment is established and maintained by the contractor for the elimination of unsafe acts by all people whilst on the project site.
8. Discuss all OHS related problems with the relevant contractor management timeously in the first instance and thereafter the Eskom project manager in the second instance relating to procedure requirements, non-conformance's identified, corrective actions, audits and inspection schedules.
9. Ensuring that quality records are maintained in accordance with legislative and Eskom requirements;
10. Continual liaison between the principal contractor, appointed contractors and employees.
11. Ensures that employees and appointed contractors are aware of latest standards, procedures, work instructions and safety regulations issued by Eskom:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

12. Conduct site Inspections for compliance to OHS requirements and compiles the relevant inspection reports.
13. Submit the observation reports to the relevant management.
14. Have meaningful participation in the project statutory health and safety committee meetings.
15. Participate in all appointed contractor incident investigations.
16. Participate in the principal contractors emergency preparedness planning.
17. Ensure that their own employees and those of any appointed contractor are competent to perform the tasks assigned.
18. Issue site instructions on behalf of the principal contractor where and when the appointed contractors deviate from safety requirements.
19. Assist the principal contractor with the handing over process, in particular the OHS file and relevant documentation.

2.5.5 Employees

Must:

1. Be responsible for their own safety and health and that of their co-workers;
2. Co-operate with their employer to meet all of the employer's as well as legislative and Eskom requirements;
3. Familiarise themselves with their responsibilities during induction and awareness training sessions, some of which are:
 - a. familiarising themselves with their workplaces and safety and health procedures;
 - b. working in a manner that does not endanger them or cause harm to others;
 - c. ensuring that the work area is kept tidy;
 - d. reporting all incidents and near misses;
 - e. protecting fellow workers against injury by performing job observations;
 - f. reporting unsafe acts and unsafe conditions;
 - g. reporting any situation that may become dangerous; and
 - h. carrying out lawful orders and obeying safety and health rules;
4. Who become aware of any person disregarding a safety notice, instruction, or regulation, immediately report this to the person concerned. If the person persists, stop that person from working, and report the matter to contractor management and/or Eskom's project manager or supervisor immediately.
5. Not damage, alter, remove, render ineffective, or interfere with anything that has been provided for the protection of the site or for the health and safety of persons this includes any guarding of machinery or equipment.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

6. Obey any safety signs and adhere to any site demarcation at all times.
7. When entering or leaving the site, do so via the official designated access/departure routes. Where reflective jackets/bibs are required to be worn, wear them.
8. Be subjected to any disciplinary action, if having transgressed any of the requirements of the health and safety site rules, Eskom requirements, company requirements, or legislative requirements.
9. Avoid any act that may endanger their own health and safety or that of fellow employees, members of the public, or visitors who may be affected by their acts and/or omissions at work.
10. Have the right to obtain proper information from their employer regarding health and safety risks and measures related to the work processes.
11. Use facilities placed at their disposal and not misuse anything provided for their own protection or that of others.
12. Have the right to remove themselves from danger when they have good reason to believe that there is an imminent and serious danger to their health and safety and have the duty to inform their supervisor immediately of such danger.
13. Report to their supervisor (in the first instance), the principal contractor (in the second instance), and/or the Eskom project manager, any substandard acts and/or conditions that have come to their attention and that have not been rectified or acted on by their contractor management timeously.
14. Have the right and the duty at any workplace to participate in ensuring healthy and safe working conditions, to the extent of their control, over the equipment and methods of work adopted.
15. Maintain the surrounding area of the work site in a neat and tidy condition.
16. Have meaningful participation in regular health and safety meetings.
17. Have the right to refuse to perform or continue to perform any task/job on the grounds of health, safety, and environmental concerns.
18. When given instructions, understand the instructions and be permitted to clarify those instructions.

2.5.6 Contractor Health and Safety officer: (Full time/Part time registered with SACPCMP)

1. Promote a OHS culture within the organisations involved in the project / contract.
2. The contractor's safety and health officer shall assist in the control of all health and safety-related matters on the sites.
3. Be involved in the developing the project OHS plan and OHS policy.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

4. Be in constant liaison and cooperate with Eskom's OHS professionals responsible for providing them with a health and safety service.
5. Ensure that this OHS specification is adhered to by his/her principal contractor and is submitted to any appointed contractors.
6. Conduct audits and inspections of all work sites for the duration of the project.
7. Be involved in the organisations incident investigations when required.
8. Participate in the organisation's statutory and non-statutory health and safety committees meetings.
9. Conduct organisational, site and visitor induction training.
10. Stop any employee or contractor from performing construction work which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.
11. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/OHS is under the influence. Furthermore, report such instances to contract management.
12. Make themselves available and ensure co-operation of employees under their control to undergo breathalyser and drug testing while entering and/or being on any Eskom work site by Eskom.
13. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor;
14. Carry out frequent behaviour observations of employees under their control at least monthly and any appointed contractors on instructions of their contractor.

2.6 Related/Supporting Documents

Eskom OHS Act section 37 (2) agreement to be signed at procurement during the signing of the NEC contract, it is the responsibility of the project manager to ensure that the 37(2) agreement is signed and a copy be kept in the contractor file at procurement.

3. Specification

3.1 Scope of work

The scope of work for MV and LV Minor and Major reticulation lines is standard throughout Eskom and was compiled by Project Execution Department and Stated as follows:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Provision of Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators within Distribution Gemma Cluster-North-West on an “as and when” required basis over a period of four (4) years.

Type 1 projects

- House connections.

Installation and replacement of smart meter and airdac/service cable

Type 2 projects

House connections.

Installation and replacement of smart meter and airdac/service cable.

Installation and replacement of meter KIOSK with landrate, rural flex and smart meters.

Extension on the LV backbone (Overhead/underground).

Type 3 Projects

House connections.

Installation and replacement of smart meter and airdac/service cable.

Extension on the LV backbone. (Overhead and underground).

Construction of lines (overhead or underground) up to 5km.

Building of transformer/Minisub structure including installation of: 16kva – 1 MVA Pole mounted.

Transformers and 200 kVA – 1MVA Mini subs.

Installation of MV and service cables (when required).

Installation and replacement of meter KIOSK with landrate, rural flex and smart meters.

Decommissioning work.

Type 4 Projects (Negotiated days) - All the above including:

Construction of lines (overhead or underground) from 500m upwards.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

All long lead material projects.

SAHRA approvals, Railway crossings, servitudes, bush clearing, Rock drilling, bulleting.

Road crossing (National, Provincial and local roads).

Line upgrades.

Type 5 and 6 Projects - All the above including:

Line construction and deviation projects up to 33kv lines.

Recoverable work.

Minor and Major Refurbishment, Strengthening Projects e.g. Feeder splits and split metering.

Eskom incurred costs

All long lead material projects.

- Project requiring dead outages.
- Self-built projects.
- SSEG/ IPP projects.

The scope will also include the following:

Installation of underground MV and LV cables including related terminations and joints up to 33Kv.

Installation of miniature substations (minisubs) and ring main units (RMUs).

Installation of load switches & section links.

Installation of transformers, reclosers, voltage regulators, CTVT (Metering Units).

Decommissioning of equipment.

And any other activity with voltage up to 33kV.

A copy of the scope of works must be retained by the contractor.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Note: The contractor who will be awarded this contract will be known as the “principal contractor” and any contractor appointed by the principal contractor will be known as the “appointed contractor”.

3.2 Legal Compliance

3.2.1 Section 37(2) (Legal) Agreement

A section 37(2) agreement must be signed between Eskom and the principal contractor at the time of awarding the contract. The principal contractor must ensure that a section 37(2) agreement is compiled between the principal contractor and all their appointed contractors for the contract.

The original copy of the section 37(2) Agreement must be retained by the contractor and a copy retained by the responsible project manager.

A copy of all the agreements must form part of the respective contractor’s OHS file.

3.2.2 Hazardous work by children (Child Labour)

The constitution of the Republic of South Africa, in the “Bill of Rights” is clear on the rights of children, especially when it comes to:

1. being protected from exploitative labour practices;
2. not to be required or permitted to perform work or provide services that
 - i. are inappropriate for a person of that child’s age; or
 - ii. place at risk the child’s well-being, education, physical or mental health or spiritual, moral or social development;

and the Basic Conditions of Employment Act, Chapter six Section 43 “Prohibition of employment of children”.

Before resorting to the use of child labour, due consideration must be given to the rights of the child in terms of the constitution. Where work is being performed which is not prohibited in terms of the constitution, then such work must be conducted in terms of the OHS Act “Regulations on Hazardous Work by Children in South Africa” with emphasis on paragraph 2

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Purpose and Interpretation. Eskom does not condone the use of child labour and therefore all effort must be exercised and child labour should not be used.

3.2.3 OHS Act

The principal contractor and appointed contractors shall have an up to date copy of the OHS Act and regulations which will be available to all employees.

3.2.4 Legislative compliance

All contractors will comply with all the legislation pertaining to this contract being:

The principal contractor and all appointed contractors will comply with all the legislation pertaining to this project being:

- The Constitution of the Republic of South Africa (particularly Section 24 of the Bill of Rights).
- Occupational Health and Safety Act 1993 (Act 85 of 1993) and its Regulations.
- National Environmental Management Act 1998 (Act 107 of 1998).
- Environment Conservation Act 1989 (Act 73 of 1989).
- National Water Act 1998 (Act 36 of 1998).
- Civil and Building Work Act.
- National Road Traffic Act 93 of 1996.
- Compensation for Occupational Injuries and Diseases Act.
- SANS Standards –Contractor shall use the relative standards applicable to the project.

3.3 Eskom Requirements

All contractors shall, before commencement of the project ensure that all their employees are familiar with the relevant Eskom OHS documentation that is applicable to contract services.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.4 Construction Professional Registration

The principal contractor and all his/her appointed contractors shall be registered in their respective levels as professionals in terms of the requirements of the SACPCMP.

The SACPCMP web address is <http://www.sacpcmp.org.za>

- OHS professionals (which include Construction Safety Officers) are required to register as professionals with the SACPCMP.
- Construction Managers are required to register as professionals with the SACPCMP.
- Construction agents are required to register as a professional with the SACPCMP.

3.5 Notification of Construction Work

Unless otherwise contractually agreed upon, the principal contractor must notify the relevant provincial director of the Department of Labour of the intention of carrying out any construction work as defined in Construction Regulation 4 of the Act. The notification form of construction work is listed as an annexure to the construction regulations of the OHS Act. A copy of the notification letter sent to the DoL shall be forwarded to the Project Manager on the same day as sent to the DoL. A copy of the letter and their approval must be kept in the OHS file. When the DoL provide a letter of approval, a copy of the approval must be sent to the Eskom Project Manager and a copy filed in the OHS file.

3.6 OHS Policy

OHS policy is a statement of intent and a commitment by the organisation's CE and senior management in relation to the relevant OHS roles and responsibilities, the achievement of their strategic objectives, values of integrity, customer satisfaction, excellence, and innovation.

The principal contractor and all appointed contractors, if already not in place, will be required to compile an organisational OHS policy in line with their OHS responsibilities. The policy must be signed by the organisation's CE or the appointed assistant to the CE OHS Act Section 16(2). The policy must be displayed in a prominent place within the workplace. A copy of the policy must be filed in the contractor OHS files and attached as an annexure in the OHS Plan.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.7 COID

The principal contractor and all his/her appointed contractors shall be registered with an appropriate employment compensation commissioner and have available a valid letter of good standing (LoG) from such commissioner. The obligation lies with the contractors to ensure that the LoG remain valid throughout the contract period. A copy of the LoG must be filed in the contractor OHS files.

3.8 Costing for OHS within the Project

The costing for OHS must be itemised based on the overall scope of the project (i.e.) Training, provision of PPE, safety equipment purchases etc.

3.9 Statutory Appointments

For the duration of the contract, the principal contractor and all appointed contractors shall appoint competent employees who will meet the requirements of the OHS Act. Where appointments are made, contractors shall ensure that the appointees have been suitably trained and informed of their responsibilities before getting them to accept such an appointment. The relevant statutory appointments shall be made in accordance with the requirements of the OHS Act which includes the requirement of a competent person being appointed in the relevant roles. The statutory appointments should include but not limited to the following:

- OHS Act Construction Regulation 8(1) - Construction Manager (Full time)|
- OHS Act Construction Regulation 8(7) – Assistant Construction Supervisor
- OHS Act Construction Regulation 8(5) – Construction Health and Safety Officer (Full time for major and part time for minor projects)
- OHS Act General Administrative Regulation 9(2) – Incident Investigator
- OHS Act Section 19 (3) - Health and Safety Committee Member
- OHS Act Section 19(6)(a) – Co-opted Health and Safety Committee member
- OHS Act Hazardous Chemical Substances Regulation 3(3) Hazardous Chemical Substances Co-coordinator

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- OHS Act, Section 17 – Health and Safety Representative.
- OHS Act General Machinery Regulation 2(1) – Supervision of Machinery
- OHS Act Construction Regulation 7(1)(V) Appointment of a Contractor (if appointing subcontractors)
- OHS Act Construction Regulation 9(1) - Person to Compile Risk Assessments
- OHS Act Construction Regulation 10(1) - Competent Person to Compile Fall Protection Plan
- OHS Act: Pressure Equipment Regulations 11 & 12 Portable Gas Container Inspector
- OHS Act: Construction Regulations 11(1) Person to Supervise Excavation Work
- OHS Act: Construction Regulations 16(1) Scaffolding Supervisor
- OHS Act: Construction Regulations 23(1)(d)(i) Construction Vehicle and Mobile Plant Operator
- OHS Act: Construction Regulations 24(c) Electrical Installations and Machinery on construction sites
- OHS Act: Construction Regulations 28(a) Stacking and Storage Supervisor on Construction sites
- OHS Act: Construction Regulations 29(h) Firefighting Equipment Inspector
- OHS Act General Safety Regulations 3(4) – First Aider/s

3.9.1 Non-statutory appointments

- Eskom requirement – Emergency Planning Co-coordinator
- Eskom requirement - Chairperson of Health and Safety Committee

3.10 Eskom Life-saving Rules

1. Eskom views health and safety in high esteem and encourages that any organisation who performs work for Eskom in Eskom adopt the same view.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. Five Life-saving rules have been developed that will apply to all Eskom Employees, agents, consultants, and **contractors**. Failure to adhere to these rules by any Eskom employee or employee of a Principal Contractor or appointed contractor will be considered a serious transgression. These rules are being implemented to prevent serious injury or death of any employee, labour broker or contractor working in any area within Eskom.
3. If any contractual work will be performed on any Eskom premises (including delivery of any product), then the rules **shall be obeyed** by any contractor and their employees.

The rules are:

RULE	DESCRIPTION OF RULE
Rule 1	OPEN, ISOLATE, TEST, EARTH, AND CREATE AN EQUIPOTENTIAL ZONE BEFORE TOUCH (That is plant, any plant operating above 1000 V)
Rule 2	HOOK UP AT HEIGHTS Working at height is defined as any work performed above a stable work surface or where a person puts himself/herself in a position where he/OHS exposes himself/herself to a fall from or into.
Rule 3	BUCKLE UP No person may drive any vehicle on Eskom business and/or on Eskom premises: Unless the driver and all passengers are wearing seat belts.
Rule 4	BE SOBER No person is allowed to be under the influence of intoxicating liquor or drugs while on duty
Rule 5	PERMIT TO WORK Where an authorisation limitation exists, no person shall work without the required permit to work.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Rule 6	Ensure live safe working
	Ensure all live work basic principles are adhered to, as outlined in the High/Low Voltage Live Working Standard.

Eskom will take a stance of zero tolerance on these rules.

Non-compliance to a Life Saving rule will be considered serious misconduct and will lead to serious disciplinary action, which may include dismissal.

This is to ensure that **every person** who works on or visits an Eskom **returns home safely to his or her family**.

3.11 Substance Abuse

1. Alcohol and substance abuse poses a significant threat to any business, more so in industrial incidents and the driving of vehicles. Eskom is therefore, entitled to take reasonable steps to ensure that intoxicated persons are identified and prevented from entering Eskom.
2. General Safety Regulation 2A is clear on the legal stance regarding intoxication.
3. The alcohol and drug permissible level is 0%.
4. All contractors shall comply with Eskom's procedure 32-37 ("Substance Abuse Procedure"), taking in to account that this is an Eskom Life-saving Rule number 4: BE SOBER", this means anyone entering the Eskom will be subjected to ad hoc alcohol testing.
5. Contractors are encouraged to compile their own manual and to carry out regular alcohol testing of their own employees. The legislative alcohol level is deemed to be zero.
6. Test records must be treated as "Confidential" and filed in the employees' personal file.

3.12 Contractor organisational Structure

3.12.1 Principal Contractor Organogram

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

The principal contractor must provide an organisational organogram related to this contract, depicting all the levels of responsibility from the CE down to the supervisors responsible for the contract. List the relevant positions held, names of appointees and legal appointments.

The principal contractor must ensure that all appointed contractors comply with this requirement. The principal contractor is responsible for keeping copies of all the organograms' as well as submitting them with the OHS plan. All organograms shall be updated timeously when appointments are changed.

This diagram must be kept up to date and filed in the project OHS files.

3.12.2 Appointed Contractor/s Organogram

1. Appointed contractors are required to compile their company organogram for the project, listing the reporting structure from their CE down to their project supervisors. The diagram must list the names, positions held and any appointments made.
2. This diagram must be kept up to date, a copy of which must be given to the principal contractor and a copy filed in the relevant project OHS files.
3. This diagram must be kept up to date and filed in the project OHS files.

3.13 Risk assessment (refer to 32-520)

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken.

It is essentially a three stage process:

- identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example if a job / task is extended over a day or halted due to inclement weather.

Guidelines for actual steps involved in a job/task specific risk assessment are:

- Each activity is listed;
- Specific hazards are identified and listed against each activity;
- The magnitude of each risk is rated as Low. Medium or High;
- All known documentary and supervisory controls are listed. For instance: What safe work procedures exist for ladders;
- The relevance, effectiveness and sufficiency of these controls are assessed;
- In the event of insufficient or deficient controls for the particular activity, steps to be taken to rectify this shall be recorded, and safe working procedures drawn up;
- Persons responsible for implementing and supervising the task shall be identified, nominated and duly assigned;
- Persons responsible for monitoring the task and carrying out the planned job observation must be nominated;
- Completed risk assessment shall be handed to the Eskom project manager representative for comment and approval.

The relevant section of the risk assessment shall be issued with a Transmittal Note to the Supervisor nominated as the responsible person; and the names of workmen who have received instruction on the work content and the sequence of the activities listed in the risk assessment shall be recorded, and their competence established. This instruction shall be done through an interpreter if required and recorded on the Pre-Job Brief (Daily Safe Task Instructions), with reference to applicable Risk Assessments.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Anticipated activities for this project (NOTE this list is not Exhaustive)

1. Driving
2. Loading and offloading of material
3. Lifting of equipment
4. Working at heights
5. Use of hand tools
6. Staking and storage
7. Working in extreme weather conditions
8. Excavation work
9. Use of electrical tools
10. Remove and replace equipment at heights
11. Go into customers yards and houses
12. Replace cable and meter kiosk
13. Use of ladders
14. Use of Vehicle mounted crane
15. Old infrastructure / poles
16. Working next to streets
17. Members of public
18. Manual Handling
19. Animals
20. Use of portable electrical tools

Pre task planning

NOTE: The Occupational Health and Safety Centre of Excellence is pleased to announce the publication of the new Distribution Standard 559-668198576:

Pre-task planning, Risk Assessment and Feedback Process for the Completion of Work, Revision 1.

This supersedes the previous Procedure DPC 34-227 Pre-task Planning and Feedback Process

The Occupational Health and Safety Act, No. 85 of 1993 imposes a duty of care on the employer and the employee alike.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Sound risk management involves effective planning and risk assessment for all work activities to ensure that any potential harm to people, or damage to equipment and plant, is eliminated or minimized.

The pre-task plan should cover all aspects of the task to be performed and ensure that the work is completed safely, considering that risks may change.

Risk management and risk assessment facilitate continual improvement of the Distribution business especially as it relates to the occupational health and safety goal of Zero Harm.

Purpose This standard outlines the step-by-step process for planning work activities, from site preparation to assessing and treating the risks, work execution, site restoration, task feedback and closure.

Applicability This document shall apply throughout Distribution and entities in which Distribution has a controlling interest, such as contractors, for all work activities executed by an individual or a team.

3.14 Safe work procedures / method statements

Method statements / written safe work procedure are control measures used to prevent an incident from occurring during the execution of the project. A written safe work procedure/ method statements provide guidance how to execute the task safely. A safe working procedure should be written when:-

- Designing a new job or task;
- Changing a job or task;
- Introducing new equipment or substances; and
the safe working procedure should identify:
- The supervisor for the task or job and the employees who will undertake the task;
- The tasks that are to be undertaken that pose risks;
- The equipment and substances that are used in these tasks;
- The control measures that have been built into these tasks;
- Any training or qualification needed to undertake the task;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- i. The personal protective equipment to be worn;
- j. Actions to be undertaken to address safety issues that may arise while undertaking the task.

3.15 Construction Sites

Note1:No area is to be stripped of vegetation to create firebreaks, to prevent or make fires. No open fires are allowed on site. The contractor must ensure that operations are in compliance with statutory requirements at all times.

1. The contractor must develop a fire safety procedure for the construction site prior to commencing work. The procedure must take into consideration the size of the site/s, the type of work performed and amount of combustible materials. Cognisance of OHS Act CR 29 must be made.
2. It must be developed in accordance with the hot work permit of the Eskom Plant Safety Regulations, Eskom Fire Risk Management requirements and all other applicable Regulations. All workers entering and working in the construction site need to be trained in fire safety and any duties they are required to perform.
3. A suitable fire warning system for alerting site personnel of fire shall be provided, and capable of being heard in all areas of the site.
4. Appropriate portable extinguisher's must be available on the construction site and in cases of hot work, be readily available at the location.
5. Storage of combustible and flammable liquid in the construction site is not permitted unless stored in approved flammable cabinets or outdoors away from the buildings.
6. Site Smoking Restrictions must be enforced. No open flames are permissible and where hot work is performed, the work areas must be cleared of any combustibles prior to commencement of work.

3.16 Fire Equipment and maintenance

1. All firefighting equipment's that have been provided shall:
 - a. Be clearly labelled
 - b. Conspicuously numbered
 - c. Entered in a register
 - d. Inspected monthly by a competent person

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. Tested and serviced at recommended intervals by an accredited supplier
3. Results entered in the register and signed by competent person.

3.17 Flammable and Combustible Liquids

1. Proposals to store fuel on site must have written approval from the Eskom Project Manager. The volumes of fuel allowed to be stored will depend on site conditions and Statutory Regulations.
2. A maximum storage of 40 litres of fuel is allowed to be stored. Anything greater than 40 litres to be stored in a flammable/combustible liquid store.
3. Adequate numbers of dry chemical fire extinguishers, each with a minimum capacity of 4.5 kg, shall be provided, installed and maintained.
4. All fuel storage areas must comply with the following requirements: -
 - a.Storage should be well clear of buildings.
 - b.Storage areas must be kept free from all combustible materials.
 - c.All Safety signs must be prominently displayed i.e.
 - Flammable Liquid.
 - No Smoking.
 - No open flames.
 - d.Adequate firefighting equipment must be available.
5. Diesel tanks are to be installed in a bunded area; bunded area must be able to contain 110% of tank capacity.
6. Bunded area shall be of a concrete or steel construction and lined with a leak proof sealing material.
7. Bunded area shall have a drain valve.
8. No other material/equipment shall be stored in the bunded area.

3.18.1 Refuelling at the construction site

With the exception of construction vehicles and mobile equipment, before a machine is refuelled, the motor must be stopped. Refuelling shall take place at designated safe areas and appropriate warning signs installed. Suitable drip trays must be used to prevent spillage at the filling nozzle.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.18 First Aid and Equipment

1. The requirements of the OHS Act GSR 3 must be observed.
2. First aid appointments must be made to meet the requirements, this includes construction sites. Appointees must be trained to level 2. It is good practice for all employees to be trained to at least level 1.
3. When appointing employees for work sites, cognisance must be taken into account the type of work performed, the distance teams are working apart and the terrain to be covered if an emergency should arise.
4. A list of emergency numbers must be displayed on the notice boards and made accessible for all employees.
5. Principal Contractor must ensure that his /her employees and appointed contractor employees are familiar with the emergency numbers.
6. Contractors shall have one first aid box for the first 5 persons and thereafter one for every 50 or team of workers on site or part thereof, taking into account the type of work performed and the distance between teams.
7. More first aid boxes shall be provided in accordance with the risk assessment. Boxes must be available and accessible for the immediate treatment of injured persons at the workplace.
8. For offices, signs indicating where the first aid box or boxes are kept as well as the name and contact details of the First Aider of such first aid box or boxes shall be erected.
9. The Principal Contractor and appointed contractor shall ensure that alternative arrangements be made for incidents occurring after working hours.

3.19.1 Boxes and equipment

The following is a list of minimum contents of a first aid box:

- Item 1: Wound cleaner/antiseptic (100ml).
- Item 2: Swabs for cleaning wounds.
- Item 3: Cotton wool for padding (100 g).
- Item 4: Sterile gauze (minimum quantity 10).
- Item 5: 1 Pair of forceps (for splinters).

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- Item 6: 1 Pair of scissors (minimum size 100 mm).
- Item 7: 1 Set of safety pins.
- Item 8: 4 Triangular bandages.
- Item 9: 4 Roller bandages (75 mm X 5 m).
- Item 10: 4 Roller bandages (100 mm X 5 m).
- Item 11: 1 Roll of elastic adhesive (25 mm X 3 m).
- Item 12: 1 Non-allergenic adhesive strip (25 mm X 3 m).
- Item 13: 1 Packet of adhesive dressing strips (minimum quantity, 10 assorted sizes).
- Item 14: 4 First aid dressings (75 mm X 100 mm).
- Item 15: 4 First aid dressings (150 mm x 200 mm).
- Item 16: 2 Straight splints.
- Item 17: 2 Pairs large and 2 pairs medium disposable latex gloves.
- Item 18: 2 CPR mouth pieces or similar devices.

A content check list must be available with all boxes and boxes shall be checked on a regular basis, kept clean and dust free.

3.19 OHS Communication Systems

Principal Contractor/s and their appointed contractors must develop a communication strategy outlining how they intend to communicate OHS issues to their staff, the mediums they will employ and how they will measure the effectiveness of their OHS communication. Below is a brief on how communication should take place. Where project meetings are conducted on site, OHS shall be included as a standing agenda point and minutes of these meetings shall be available on site at all times. Minutes of meeting must be compiled and filed in the relevant OHS files. All employees shall have access to these minutes. Attendance register shall be kept for all the health and safety meetings.

3.20.1 Statutory Health and Safety Committees

1. The principal contractor shall establish statutory health and safety committee in terms of Section 19 of the OHS Act, Act. Similarly, appointed contractors shall establish their own statutory health and safety committee.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. All appointed contractors shall be members of the principal contractor's safety committee.
3. The Committee shall meet to discuss OHS issues concerning the current work being performed, training, upcoming work and OHS requirements, incidents and lessons learned specific OHS problems, safety performance, action plans and other relevant OHS issues. Listed below is a preferred agenda.
4. OHS representatives for a workplace shall be members of the relevant workplace safety committees (Refer to Section 19 (2) (a) of the OHS Act).
5. The number of persons nominated by employer must not be more than the Health and Safety Representatives on that specific statutory health and safety committee. (Refer to Section 19(2)(c) of the OHS Act)
6. A statutory health and safety committee meeting shall be held at least 3 monthly (where medium to high risk work is involved, more frequent if required), and all appointed members of the committee shall attend the meeting.
7. Statutory health and safety committees may make recommendations to the principal contractor and the project manager and the Inspector at DoL.
8. All health and safety committees shall discuss all projects related OHS Act Section 24 and 25 incidents and other notified serious incidents.
9. Health and safety committees shall follow up on incident investigation recommendations and shall keep record of all recommendations made by the committee.
10. Statutory health and safety committees may make recommendations for the revision of current standards, procedures and practices.
11. The principal contractor and appointed contractors shall ensure that statutory and non-statutory health and safety committees carry out their duties.
12. The chairperson of the health and safety committees shall be selected and appointed by the contractor. The appointed chairperson must be competent to chair meetings and be able to make informed decisions.

3.20.2 Non-statutory health and safety committees

1. Where there are large worksites, then non-statutory sub-committee must be established within that worksite to assist with the communication of health and safety related matters between the statutory health and safety committee and the workplace.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. The duties and responsibilities of the non- statutory health and safety committees will be the same as the statutory safety committee

3.20.3 Agenda

1. The following serves as the guideline for the OHS Committee meeting agenda.
 - List of agenda items:
 - Matters arising from previous minutes
 - Matters arising from Contractor's OHS meetings.
 - Audit results and feedback
 - Review Health and Safety Representative Inspection Reports
 - Review
 - Incident investigation reports
 - Non-Conformances
 - Announcements (near miss/injury/damage)
 - Follow up on recommendations made by the employer in incident investigation reports
 - Accident Prevention – Safety Promotion
 - Planned Job Observations
 - OHS Training
 - Protective clothing and equipment
 - Incident Announcements / Recall
 - Forthcoming High hazard activities.
 - Non-conformances.
 - Housekeeping.
 - Work permits.
 - Work procedures.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- Hazardous materials / substances.
- Fire Prevention
- Occupational Hygiene Assessments, Health Risks and Actions
- Security
- Construction vehicles and mobile equipment
- Rules, Instructions
- Public Safety
- Environmental Management
- Emergency Preparedness
- Statistics report
- Closure

3.20.4 Minutes and action items for all health and safety committee meetings

1. Minutes and record of action items shall be kept of all health and safety committee meetings.
2. Action column with target dates and responsible person shall be clearly visible on the minutes and shall be completed during the meeting.
3. Statutory health and safety committee meeting minutes and record of action items shall be kept for the duration of the project or a minimum period of three years.
4. Non-statutory health and safety committee meeting minutes shall be kept for the duration of the project or a minimum period of 12 months.
5. All other meeting minutes where OHS is on the agenda, shall be kept for a minimum period of 12 months.
6. The original copy of the minutes and record of the action items must be signed by the chairperson.
7. The relevant project manager and principal contractor shall endorse the relevant minutes with his/her recommendations and return the minutes to the relevant contractors chairperson within 14 calendar days of the meeting.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.20.5 Tool box talks / Daily team talks / pre job meetings

1. A meeting must be held prior to the commencement of the day's work with all relevant personnel associated with the work task in attendance. The job, relevant procedures, associated hazards, safety measures, i.e. the task risk assessments shall be discussed. Each employee who attends the briefing shall sign an attendance list of that pre-job brief form undertaking that they have an understanding of the tasks, risks and control measures required.
2. Where possible, tool box talks can be included in the pre-job brief meetings. If this does not occur, then weekly tool box talks must be conducted. The toolbox talk topics will be based on OHS issues pertaining to the construction site and or the project. The topic contents shall be in writing. Attendance registers with the topic listed shall be kept.

3.20 OHS Training

1. The principal contractor, when making a bid for this project shall provide a breakdown list of the OHS training requirements and the costing of such requirements. Similarly, appointed contractor must provide the same requirements when bidding with the principal contractor.
2. The scope of training includes but is not limited to the type of work being performed and the relevant procedures. Additional to the requirements, will be that the principal contractor and appointed contractors must have the appropriate qualifications, certificates and employees should always be under competent supervision.
3. Where legislative and Eskom recommended appointments are made, the relevant training shall be given to those appointees prior to the acceptance of those appointments.
4. When there is an amendment to the Acts and/or to the regulations, OHS specification and OHS plan, all affected staff shall undergo the applicable OHS training.
5. Appropriate time must be set aside for training (induction and other) of all employees.
6. Records of all training and qualifications of all contractor employees must be kept on the OHS file.

3.21.1 Induction training

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

1. The principal contractor shall ensure that all his / her employees, appointed contractors and their employees have undergone the Eskom Safety Contractor Management induction training prior to commencing work on site.
2. Attendance registers must be completed of any induction training given, which must indicate that they have received and understood the induction training.
3. Prior to attending the induction training, all employees must undergo a pre-employment medical examination and found fit for duty. A copy of the certificate of fitness must be kept in the OHS file on site for the duration of the project.
4. All employees and visitors on site shall carry the proof of induction training.

3.21.2 Site specific induction training

The principal contractor shall ensure that all his / her employees and appointed contractor employees undergo site specific work induction regarding the approved project OHS plan, general hazards prevalent on the construction site, construction risk assessment, rules and regulations, and other related aspects. The induction training should also include identification of sensitive features such as wetlands/vlei areas, red data species, graves, etc.

3.21.3 Visitors to site induction

1. Visitors to the site shall be required to undergo and comply with the principal contractor's site-specific safety induction prior to being allowed access to site.
2. All visitors must remain in the care and custody of a person (host) who has been properly inducted. No visitors are permitted to undertake any work onsite, of any nature.
3. Visitors who have completed site induction must be provided with a record of proof of Induction training.

3.21.4 General training

The principal contractor will be required to ensure that before an employee commences work on the project, the respective supervisor informs the employee of his scope of authority, the hazards associated with work as well as the control measures to be taken. This will include man-job specifications, the discussion of any task procedures or hazardous operational procedures to be performed by the employee. The Principal Contractor is to ensure that the supervisor has satisfied himself that the employee understands the hazards associated with any work to be performed by conducting task/job observations.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.21 Contractor Site Establishment

1. Principal contractor's site facilities should be managed at all times.
2. Prior to establishing a project site, a site plan is required to be drawn listing position of all buildings, amenities, storage and stacking areas. The appropriate colour coding and demarcation of storage and stacking areas must be carried out.
3. Where, working in the field and material is stored at the work sites, then proper stacking and storage shall be carried out.
4. When compiling the site plan, cognisance must be taken to the establishment of the site camp, ablution facilities and dining area in relation to one another and away from stacking and storage areas.

3.22.1 Site roads

1. When planning, sufficient areas must be allocated for parking of construction vehicles and mobile equipment's as well as roadways for ease of manoeuvrability of these vehicles.
2. Sufficient width roads to be provided and adequate space is to be allowed for large vehicles traversing the sites.

3.22.2 Construction vehicle safety

1. It is the responsibility of the driver to ensure:
 - a. Their passengers wear seat belts whilst the vehicle is in motion.
 - b. Comply with all traffic road rules, safety, direction and speed signs.
 - c. Ensure that vehicle loads are properly secured prior to moving off.
 - d. Ensure that vehicles are not overloaded.
2. No drivers or operators may text, talk on cell phones or two way radios whilst driving, unless a hands free kit is used.
3. All drivers of construction vehicles are to have valid medical fitness certificates.
4. Each Project site that is enclosed by demarcation will have system/ process to manage vehicle access to site.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

5. Contractor must maintain their vehicles in a roadworthy condition and a vehicle license must be valid at all times.
6. Drivers of light vehicles must avoid stopping or parking in the vicinity of machines. At least 30 (thirty) meters must be left clear between such a vehicle and such a machine
7. Contractor vehicles can be subject to inspections by the Client/Agent's representative. Vehicles which are not roadworthy will not be permitted to be used on the project.
8. Drivers/operators shall be responsible for the travel-worthiness of all loads conveyed by them. Precautions shall be taken to secure all loads properly. Loads projecting from vehicles shall be securely loaded and in daytime a red flag and during darkness a red light or red reflective material shall be attached to the extreme end of such projecting material.

3.22 Housekeeping and Order

1. All contractors shall maintain a high standard of housekeeping within their sites and vehicles for the duration of the project.
2. Prompt disposal of waste materials, scrap and rubbish is essential.
3. Materials/objects shall not be left unsecured in elevated areas –falling objects may cause serious injuries/fatalities.
4. Nails protruding through timber shall be bent over or removed so as not to cause injury.
5. All packaging material including boxes, pallets, crates, etc. to be removed from the work area immediately.
6. On completion of his / her work, the contractor is responsible for clearing his / her work area of all materials, scrap, temporary buildings and building bases to the satisfaction of the client/agent.
7. In cases where an inadequate standard of housekeeping has developed, compromising safety and cleanliness, anyone has the responsibility to bring it to the attention of the principal contractor in the first instance and the Eskom project/site manager in the second instance.
8. The Eskom Project/Site Manager has the right to instruct the principal contractor and appointed contractors to cease work until the area has been tidied up and made safe. Neither additional costs nor extension of time to the contract shall be allowed as a result of such a stoppage. Failure to comply with this requirement will result into site cleaning by another cleaning contractor company at the cost of the principal contractor.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

9. The principal contractor shall carry out regular safety/housekeeping inspections (at least weekly) to ensure maintenance of satisfactory standards. The principal contractor shall document the results of each inspection and shall maintain records for viewing.

3.23.1 Stacking

1. Before stacking any material, the contractors or their employees must consult the contract manager for authorisation to use such an area for stacking purposes. This is to prevent haphazard arrangements.
2. Adequate care must be taken by the contractor to ensure that storage and stacking is carried out correctly and safely.
3. Correct stacking must be carried out, heavy and bulky on the bottom, light and small on top.

3.23 Workplace Signage and Colour Coding

1. Symbolic safety signage shall be displayed where it is required by legislation.
2. All symbolic safety signage shall conform to the requirements of SANS standard 1186.
3. Signs shall be positioned to be seen from most positions within the work sites / areas.
4. All signage must be clear at all times and be replaced timeously when worn out.
5. Contractors establishing sites must erect a company sign at their site offices to reflect the name and contact details of the: Construction Supervisor; Health and Safety Manager/Practitioner; First Aider; Health and Safety Representative and Evacuation warden.
6. The location of every first aid box; fire extinguisher and emergency exit is to be clearly indicated by means of a sign.
7. When using, an explosive power tool the appropriate signage shall be erected, warning people of its use.
8. Contractors shall provide signage where work is conducted and where unauthorised entry is prohibited and/or where alerting and cautioning passers-by to be aware of potential dangers.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

9. The meanings of the appropriate symbolic signage must be discussed during induction training and toolbox talks.
10. Where possible, within workshops, work areas and established premises, the appropriate sign indicating the meaning of symbolic safety signs must be displayed.

3.24 Tools and Equipment

1. Contractors shall ensure that all tools and equipment are identified, safe to be used and is maintained in a good condition.
2. Contractors shall ensure that all tools and equipment are listed on an inventory list, be regularly inspected at least monthly or as required by legislation and risk assessments. The equipment should be numbered or tagged so that it can be properly monitored and inspected.
3. Where applicable, tools and equipment must have the necessary approved test or calibration documentation prior to being brought onto the project and the records shall form part of the OHS plan. Maintenance calibration shall be undertaken in terms of the manufacturer's requirements.
4. All fuel driven equipment must be properly maintained in accordance with the manufacturer's recommendations and legal requirements.
5. Eskom reserves the right to inspect tools or items of equipment brought to site by contractors for use on this project.
6. Should Eskom personnel find any item that is inadequate, faulty, unsafe or in any other way unsuitable for the safe and satisfactory execution of the work for which it is intended, the Eskom personnel shall advise the contractor in writing and the contractor shall forthwith remove the item from site and replace it with a safe and adequate substitute.

Note: In such cases, the contractor shall not be entitled to extra payments or extensions of time in respect of delay caused by Eskom's instructions.

7. Where defective tools and equipment's are identified, such tools and equipment shall be removed out of site immediately, locked away to prevent further use until such time as the tool or piece of equipment has been repaired.
8. Contractors shall ensure that the appropriate records are kept for all tools and equipment used on the project. Such tools and equipment's shall be subjected to regular inspections.

3.25.1 Hand tools

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

1. All hand tools (hammers, chisels, spanners, etc.) must be recorded on a register and inspected by the construction supervisor on a monthly basis as well as by users prior to use.
2. Tools with sharp points in tool boxes must be protected with a cover.
3. All files and similar tools must be fitted with handles.
4. No make shift tools are permissible on the project.

3.25 Ladders

1. Ladders used shall conform to the requirements of GSR 13A and used in terms of GSR 6.
2. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons.
3. The ladder wheels, brakes and platform must be in good condition.
4. All metal parts to be in good condition, no cracks.
5. Non-slip devices must be in good condition and no paint to be on wooden ladders
6. Climbing irons are permitted to be used in place of ladders on condition that the requirements of GSR 6 are not compromised and from an electrical point of view not damage any cabling. The working at heights risk assessment must indicate the use of climbing irons.
7. Employees using climbing irons shall be suitably trained in the use, care and maintenance of such climbing irons.
8. When using climbing irons, the appropriate rope grab fall prevention system shall be used.
9. The correct fall protection equipment shall be worn and used whilst climbing up, working from and climbing down ladders.
10. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons.
11. A detailed inspection of all ladders shall be conducted monthly by a competent person and every time prior to climbing by employees using such ladders. The inspection check lists must be filed in the site OHS files.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.26 Auditing

3.28.1 Approval and compliance of principal contractor OHS plan

The Contractor's OHS Plan will be audited against compliance checklist so as to verify compliance to the requirements of the Eskom OHS specifications. Once there is compliance only then will the principal contractors OHS plan be approved by the project manager or an appointed Eskom contract custodian. The implementation of the OHS Plan shall be assessed / audited by Eskom personnel on a regular basis. This will include physical conditions evaluation.

3.28.2 Eskom OHS audits

Eskom shall evaluate all contractors OHS performance on an ongoing basis against the legal, Eskom requirements, OHS specification and the contractors OHS plans.

Note: Eskom reserves the right to conduct unannounced audits on contractors

There will be monthly audits conducted by Eskom on the principal contractor/s and/or appointed contractors. These audits shall be attended by the contractor's site manager or his representative.

If there are any findings / non-compliance identified as serious in these audits, an activity will be stopped for that specific Principal Contractor and appointed contractor. Refer to section on "Work Stoppage" in this OHS Specification.

3.28.3 Contractor audits

Principal Contractors are required to conduct internal audits on both their employees and their appointed contractors on the implementation of their OHS Plan on a monthly basis or when the scope of work changes. A summary of the findings and the proposed corrective actions shall be submitted to Eskom project manager within one week after completion of the audit. Where appointed contractors are audited by the principal contractor a copy of the audit report shall be submitted to the appointed contractor within 7 days of the audit.

3.27 Smoking

The Tobacco products control act 83 of 1993 must be observed and smoking is permitted in designated areas only (Eskom Smoking Procedure 32-36).

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.28 Cellular Phones

The national requirements regarding the use of cellular phones must be observed, in particular when driving and or operating mobile equipment and or machinery.

3.29 Occupational Health, Hygiene and Rehabilitation

All contractors are required to develop an Occupational Health, Hygiene and Rehabilitation program. The program is intended to ensure that the risks to health are identified and controlled.

3.31.1 Medicals

Note: Eskom will only accept medical surveillances conducted by an Occupational Health Practitioner who holds a qualification in occupational health.

1. Principal contractors must ensure that their employees and their appointed contractor employees have a medical surveillance program whereby their employees under go entry, periodic and exit medical fitness examinations.
2. In order for the appropriate medical examinations to be conducted, each employee must have a man job specification, which must indicate the description of work, list of hazards and potential occupational exposure limits, physical hazards and required physical attributes.
3. Medical fitness certificates shall be renewed annually for employees who are working on site. This shall be maintained until completion of the contract.
4. The Principal Contractor must ensure that his / her employees and appointed contractor employees have undergone pre-entry medical examination before starting work on the contract.
5. The principal contractor shall provide a documented process for managing those employees who are issued with a conditional certificate of fitness.

3.30 Working at Heights

3.32.1 General Requirements

Wherever reasonably practicable, preference is given to the performance of work at ground level as opposed to the elevated position. Where work in an elevated position is necessary,

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

preference is given to fall prevention measures such as, but not limited to, effective barricading and the use of work platforms. Persons may only work from a fall risk position if a site-specific fall protection plan is in place and correctly implemented and consists of the following:

1. All appointments for the fall protection plan developer and implementer are in place.
2. Baseline risk assessment, which is specific and incorporates the working at height risk assessment, as well as the site-specific risk assessment, has been completed for the work to be conducted.
3. Safe working procedure/task analysis and work instructions, approved by a competent person, are in place.
4. A fall rescue plan, along with necessary equipment and trained rescuers, is in place.
5. Appropriate training, as determined by the risk assessment, has been provided.
6. Appropriate height safety equipment and personal protective equipment have been issued to the individual.
7. There are equipment inspection procedures and up-to-date inspection records.
8. Individuals are medically fit to work at height, and records of this are kept.
9. A site-specific risk assessment is performed.

While work is in progress, adequate warning signs and/or barricades shall be used in all areas where there is a risk of persons being injured by materials or equipment falling from the work area. Barricades should be continuous and easily visible.

A drop zone shall be established with appropriate warning signs and barricading, warning personnel below of workers above and potential falling objects.

Every employer shall ensure that work at height is:

1. properly planned;
2. appropriately supervised; and
3. carried out in a manner that is, as far as is reasonably practicable, safe and that its planning includes the selection of work equipment.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.31 Risk Assessments

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken. It is essentially a three stage process:

- identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example if a job / task is extended over a day or halted due to inclement weather.

3.32 Safe Work Procedures and Practices / Safe Operating

There must be written safe work procedures for emergency work and all activities, the safe work procedures must be aligned with the risk assessments.

3.33 Personal Protective Equipment Requirements

1. The Principal contractor must provide a detailed programme that includes the issuing, maintenance and replacement of PPE for all his employees and appointed contractors on site.
2. All contractors shall comply with the requirements of GSR 2 of the OHS Act.
3. The risk based PPE matrix must be compiled detailing the types of PPE that is required to be issued to employees performing the respective tasks.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

4. Where there are unusual instances where particular activities require additional type of PPE, then a risk assessment must be conducted where such PPE requirements will be identified and the issuing be carried out.
5. All contractors shall ensure that their visitors wear and use the correct PPE whilst on worksites.
6. Where PPE is required and visitors are not in possession of, then it is the individual contractor's responsibility to provide the PPE.
7. All PPE purchased and used by all contractor employees including visitors must comply with the relevant SANS standards.
8. Where deemed as a requirement, then high visibility vests shall be worn.

3.34 Incident Investigation

All incidents shall be investigated in terms of OHS Act General Administrative Regulations 8 and 9, using Eskom Procedure 32-95 as a reference, and where injuries as contemplated in sections 24 and 25 have been sustained, be reported to the Department of Labour.

Contractors shall use the standard General Administrative Regulation Annexure 1 "Recording of an Incident" form for all incident investigation reports. The objective of incident investigation should not only be a legal requirement, but should establish why and how the incident occurred and find out the real root cause of the incident and to decide on precautionary measures that are required to address the root cause to prevent any further recurrences of the same or similar incidents.

The contractor incident management procedure need to be aligned to Eskom's 32-95 incident management procedure and timeline must be strictly adhered to.

The high level steps of the incident management procedure are as follows:

1. Incident identification
2. Initiation and Execution of Emergency Response
3. Notification and Reporting
4. Incident prioritisation
5. Classification and Recording of Incidents
6. Incident investigation
7. Management of Corrective Actions (Safety Measures)

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

8. Incident close-out
9. Incident Communication

Timelines with regards to incident management need to be strictly adhered to as per 32-95 Occupational Health and Safety Incident Management Procedure and 240-131838225 Occupational Health and Safety Incident Management Definitions and Classification Parameters.

Failure to comply with these requirements will be seen as the contractor not fulfilling their contractual obligations and the relevant consequence management actions will be taken against contractors who do not comply.

Timelines include:

1. Notification of incident to relevant Eskom OHSQS department should be done before the end of shift or within 24 hours of the incident occurring.
2. Investigation process to be initiated within 48 hours and concluded within 30 calendar days. The onus is on the contractor manager to provide evidence for the reasons why the Internal OHS Investigation could not be completed within 30 days and should be submitted to the relevant OHSQS department.

In the case of incidents involving contractor employees, the contractor must investigate those incidents as an employer in his/her own right (employer's investigation) and generate a report. The report and Annexure 1 must be submitted to the applicable OU/BU or on request to the Department of Labour by the contractor. Eskom may participate during these investigations.

3.35 Emergency Management

The art of emergency preparedness and response is to minimise the effects of any emergency and to restore normal activities as soon as practical. The contractor must familiarise themselves with the Eskom emergency response plan and procedure. Periodic emergency drills must be undertaken to test the effectiveness of the plan. This must be recorded and provided to the Eskom OHSQS department for evaluation in the site specific safety file.

The emergency management procedure to be submitted has to include emergency contact numbers relevant to the area worked in for the site supervisor, hospital, fire brigade, first aider.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

If no cellular phone reception is present for example in remote areas, an adequate process must be put in place to have adequate alternative communication.

3.36 Non-Conformance and Compliance

1. Any non-compliance to any health and safety requirement in this OHS specification is subject to discipline in terms of the Eskom Procurement and Supply Management Procedure.
2. Principal contractors are required to implement a non-conformance procedure (if not already in place) for issuing to contractors for transgressions. The procedure can include “quality” related non-conformance issues. Similarly, appointed contractors must implement a non-conformance procedure.
3. The procedure for the issuing and closing off of non-conformance reports shall be strictly adhered to.
4. Contractor project management must monitor the close out non-conformances issued, in not doing so; any recommendations made may not be implemented.
5. Where non-conformances are issued by Eskom then one of the close-out steps of the procedure will be for the offender to be called by the responsible project manager to explain the non-conformance issued and what plan is in place to prevent a recurrence of the non-conformance.
6. Should the contractor fail to provide adequate PPE to their employees for the tasks being performed and/or to visitors; failure to enforce the wearing of such PPE will be viewed as a transgression of the legislative and Eskom requirements.
7. After a contractor has been appointed a site specific safety file needs to be developed and submitted to the Eskom OHSQS department for evaluation. No contractor may commence with work before the site specific safety file is accepted and the site specific procedures are adhered to.
8. If a safety file reaches 80% compliance the contractor may enter the site under certain conditions. The sections of the file that is not approved may have a knock on effect on operations whereby certain duties may not commence due to the safety file requirements not being met. The sections of the file that is not approved on, work cannot commence.
9. Eskom reserves the right to stop any contractor performing unsafe work/conditions and can apply consequence management if any contractor fails to comply with any Legislative requirements as well as any Eskom Requirements, Standards and

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Procedures. Refer to 32-726 OHS Requirements for the Eskom Commercial Process Section 3.4.4.4.

10. Should Eskom personnel find that the site-specific safety file is unsatisfactory, the process in Section 3.7 of 32-726 OHS Requirements for the Eskom Commercial Process shall be initiated.

3.37 OHS File

1. A OHS file means a file or other record in permanent form, containing the information about the safety and health management system during construction and all information relating to the post-construction phase after handover to the client, so that the client can maintain the works in a healthy and safe way.
2. All contractors are required to keep a OHS file on every project site. If there is more than one site per project, a file per site shall be kept at that site. Contractors may keep additional files at their head office as additional records. The OHS file shall be maintained by all the contractors on their construction sites and shall be available on request for audit and inspection purposes.
3. The OHS file shall consist of the requirements in terms of the project's safety specification, the contractor's safety and health plans.
4. The sequence of filing the documentation must be kept in the same sequence as listed in this OHS specification and the OHS plan.
5. Each record shall be separated by partitions to afford easy identification and access. Each partition must be labelled.
6. On completion of the construction work/project, the principal contractor must hand over a consolidated health and safety file to the project manager. The principal contractor must also hand over all drawings, designs, lists of materials used, and other applicable information about the completed structure, as well as the list of subcontractors, the agreement, and the type of work completed.
7. In case where the project is extended, should the documentation in the OHS files become cumbersome, the older documentation must be archived in boxes which shall be correctly labelled and be available for auditing purposes. The archived documentation must be handed over at the completion of the project.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.38 Work Stoppage

1. Any person may stop any activity where an unsafe act or unsafe condition that poses or may pose an imminent threat to the safety and health of an individual or create a risk of degradation of the environment. This includes any unauthorised work or service performed by, or legally or contractually non-compliant acts or omissions by, any contractor contracted to work at that site.
2. Work stoppages that are initiated due to OHS concerns, non-compliance, or poor performance related to the contractor's works or services shall not warrant any financial compensation claim lodged against Eskom where the contractor has not met the requirements defined legally or contractually.
3. Where stoppages are carried out, the required non-conformance report shall be raised.
4. All work stoppages ideally should be investigated and documented by contract custodians.

3.39 Hours of Work

The requirements of the Basic Conditions of Employment Act, Chapter Two "Regulation of Working Time" must be adhered to. All contractors are required to maintain an accurate record of time worked by each employee.

3.41.1 Normal work

All work conducted on site shall fall within the legal requirements in accordance with the Basic Conditions of Employment Act. Contractors will notify their Eskom Supervisor or project manager of any work that needs to be performed after hours according to the agreed arrangements. (The application needs to be submitted timeously). Where applicable, the notification should include proof of application, for overtime, to the Department of Labour and /or the letter of approval from the Department of Labour.

3.41.2 Night work

When night work is to be performed; contractors shall provide sufficient lighting to enable the entire work site to be illuminated to a degree that employees will not work in dark (un-illuminated) or dimly lit areas. Care must be exercised as not to use few lights with high light intensives as this will cause night blindness.

If work is continuing from day light into night, at dusk, a toolbox talk must be held where all employees will be advised of the hazards of night work and the extra precautions which require to be taken, i.e. poor housekeeping, stepping on uneven ground, stepping into holes etc.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.41.3 Overtime

When overtime is required to be performed, the appointed contractors shall inform the principal contractor of such action. The principal contractor shall inform the Eskom project manager of such function. Contractors shall be aware of the effects of human fatigue and regulate overtime accordingly. The baseline risk assessment must be reviewed to include the management of overtime work.

3.40 Omissions from Safety and Health Requirements Specification

By drawing up this OHS specification Eskom has endeavoured to address the most critical aspects relating to OHS issues to assist the contractor to adequately provide for the health and safety of employees on site.

Should Eskom not have addressed all OHSQ aspects pertaining to the work that is tendered for, the contractor needs to include it in the OHS plan and inform Eskom of such issues when signing the contract.

3.41 4

On completion of the project, all appointed contractors shall close out their project documentation; OHS files and forward such to the principal contractor. The principal contractor shall likewise close out his/her project documentation and OHS files and forward such to the Eskom project manager.

3.42 Project Statistics

The following information should be submitted by the 1st of each month to the Contract Manager/ Custodian:

- Contractor manpower numbers and hours worked for the purpose of calculating the contractor lost-time injury (LTIR) and total recordable injury (TRIR) rates
- Contractor incidents per month (fatalities, lost time, medicals, first aid and near-misses).
- Contractor confirmation that incident case studies were discussed and recommendations implemented.
- Contractor confirms that all issues findings against them has been addressed as required.
- Contractor will submit their statistics every month using the latest 240-140441286 Contractor Manpower/Man-hours and OHS stats reporting form.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.43 Weather Extremes

Contractors should, after conducting a site-specific baseline risk assessment establish what weather extremes are occurring in the area and make provision for control measures to prevent or reduce exposure to their employees to an acceptable level.

3.44 Dismantling, Assembly and Erecting of Structures

Construction Regulations 10, 11 and 14 needs to be strictly adhered to.

A competent person needs to be appointed to supervise demolition work in terms of Construction Regulation 14(1).

Contractors need to take all reasonable steps to prevent the uncontrolled collapse of any new or existing structure or any part of the said structure that may become unstable, or which might be in a temporary state of weakness or might be unstable due to carrying out construction work.

No structure or part of any structure may be loaded in such a manner that it would be deemed as unsafe.

A contractor needs to appoint a competent person in writing to supervise and control all demolition work on site.

Before any demolition work is being carried out a competent person need to develop a detailed structural engineering survey of the structure to be demolished in order to identify the order in which the structure needs to be demolished. The competent person who develops the structural engineering survey also needs to provide a method statement on the procedure to be followed in demolishing the structure.

The appointed competent person on supervising demolition work must check the structural integrity of the structure being dismantled at regular intervals determined by the method statement in order to prevent any premature collapse.

Contractors involved with demolition work need to take steps to ensure that no person works under overhanging material or a structure which has not been adequately supported, shored or braced. Steps should be taken by contractors to ensure all other services in the vicinity that may be affected are rendered safe for all persons involved.

Where demolition work includes working at heights and there is a risk of falling objects the following needs to be in place: (32-418)

1. A drop zone must be established and demarcated.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

2. Suitable steps must be taken to prevent any material or objects from falling that could cause harm to people or property.
3. Where it is not reasonably practicable to comply with the requirements of paragraph 2 every employer must take suitable and sufficient steps to prevent any person from being struck by any falling material or object that is liable to cause personal injury.
4. No material or object shall be thrown or tipped from height in circumstances where it is likely to cause injury to any person.
5. Materials and objects must be stored in such a way as to prevent risk to any person arising from the collapse, overturning or unintended movement of such materials or objects.

Where demolition work includes working at a fall risk position a site-specific fall protection plan needs to be developed and implemented by a competent person as per Construction Regulation 10.

The fall protection plan should make provision for the following information:

1. a risk assessment of all work carried out from a fall risk position and the procedures and methods used to address all the risks identified per location;
2. the processes for the evaluation of the employees' medical fitness necessary to work at a fall risk position and the records thereof;
3. a programme for the training of employees working from a fall risk position and the records thereof;
4. the procedure addressing the inspection, testing and maintenance of all fall protection equipment;
5. A rescue plan detailing the necessary procedure, personnel and suitable equipment required to affect a rescue of a person in the event of a fall incident to ensure that the rescue procedure is implemented immediately following the incident.

Contractors to ensure that the Fall Protection Plan is site specific as well as scope of work specific and that all required legislation as well as the Eskom requirements are adequately met.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.45 Excavation Work

As per the scope of this project excavation will take place and as a result strict adherence to Eskom and legislative requirements need to be adhered to pertaining excavations.

As per Construction Regulation 13 – Excavations:

- (1) A contractor must-
 - (a) ensure that all excavation work is carried out under the supervision of a competent person who has been appointed in writing for that purpose; and
 - (b) evaluate, as far as is reasonably practicable, the stability of the ground before excavation work begins.
- (2) A contractor who performs excavation work-
 - (a) must take reasonable and sufficient steps in order to prevent, as far as is reasonably practicable, any person from being buried or trapped by a fall or dislodgement of material in an excavation;
 - (b) may not require or permit any person to work in an excavation which has not been adequately shored or braced: Provided that shoring and bracing may not be necessary where-
 - (i) the sides of the excavation are sloped to at least the maximum angle of repose measured relative to the horizontal plane; or
 - (ii) such an excavation is in stable material: Provided that-
 - (aa) permission has been given in writing by the appointed competent person contemplated in subregulation (1) upon evaluation by him or her of the site conditions; and
 - (bb) where any uncertainty pertaining to the stability of the soil still exists, the decision from a professional engineer or a professional technologist competent in

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

excavations is decisive and such a decision must be noted in writing and signed by both the competent person contemplated in subregulation (1) and the professional engineer or technologist, as the case may be;

(c) must take steps to ensure that the shoring or bracing contemplated in paragraph (b) is designed and constructed in a manner that renders it strong enough to support the sides of the excavation in question;

(d) must ensure that no load, material, plant or equipment is placed or moved near the edge of any excavation where it may cause its collapse and consequently endangers the safety of any person, unless precautions such as the provision of sufficient and suitable shoring or bracing are taken to prevent the sides from collapsing;

(e) must ensure that where the stability of an adjoining building, structure or road is likely to be affected by the making of an excavation, steps are taken to ensure the stability of such building, structure or road and the safety of persons;

(f) must cause convenient and safe means of access to be provided to every excavation in which persons are required to work, and such access may not be further than six meters from the point where any worker within the excavation is working;

(g) must ascertain, as far as is reasonably practicable, the location and nature of electricity, water, gas or other similar services which may in any way be affected by the work to be performed, and must before the commencement of excavation work that may affect any such service, take the steps that are necessary to render the circumstances safe for all persons involved;

(h) must ensure that every excavation, including all bracing and shoring, is inspected-

(i) daily, prior to the commencement of each shift;

(ii) after every blasting operation;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- (iii) after an unexpected fall of ground;
- (iv) after damage to supports; and
- (v) after rain,

by the competent person contemplated in subregulation (1), in order to ensure the safety of the excavation and of persons, and those results must be recorded in a register kept on site and made available on request to an inspector, the client, the client's agent, any other contractor or any employee;

- (i) must cause every excavation which is accessible to the public or which is adjacent to public roads or thoroughfares, or whereby the safety of persons may be endangered, to be-
 - (i) adequately protected by a barrier or fence of at least one metre in height and as close to the excavation as is practicable; and
 - (ii) provided with warning illuminates or any other clearly visible boundary indicators at night or when visibility is poor, or have resort to any other suitable and sufficient precautionary measure where subparagraphs (i) and (ii) are not practicable;
- (j) must ensure that all precautionary measures stipulated for confined spaces as determined in the General Safety Regulations, 2003, are complied with by any person entering any excavation;
- (k) must, where the excavation work involves the use of explosives, appoint a competent person in the use of explosives for excavation, and must ensure that a method statement is developed by that person in accordance with the applicable explosives legislation; and
- (l) must cause warning signs to be positioned next to an excavation within which or where persons are working or carrying out inspections or tests.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3.50 Existing Infrastructure and Services

Before any work commences the Principal contractor should ensure that all existing infrastructure (Live overhead feeders, underground networks such as water pipes electrical cables etc.) are known to their employees and the risks pertaining to these infrastructure as well as what control measures are in place to ensure that no employees is injured or infrastructure damaged as a result of their activities.

The relevant existing infrastructure hazards and risks should be identified and included in the project specific baseline risk assessment together with the relevant control measures.

Acceptance

Nil.

3. Revisions

Date	Rev.	Compiler	Remarks
August 2015	0	F Poee	This provides the initial OHS specification requirements that must be met by the relevant contractors who have been awarded a contract for the work to be performed for Eskom.
	1		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

ANNEXURE 1 – FLASH REPORT

ACCIDENT / INCIDENT REGISTER NO :

PART 1 – TO BE COMPLETED FOR ALL ACCIDENTS / INCIDENTS:

ESKOM ☐
PUBLIC ☐
CONTRACTOR ☐
CASUAL/TEMP ☐

POOL ☐
COMPANY CAR ☐
SCHEME ☐
HIRED/PRIVATE ☐

FIRST AID		ELECTRICAL CONTACT	
MEDICAL		EQUIPMENT DAMAGE	
FATAL		THEFT	
LOST TIME INJURY		ENVIRONMENTAL	
OCCUPATIONAL DISEASE		FIRE	
VEHICLE ACCIDENT		NEAR MISS	
STORM DAMAGE		ON DUTY	
OTHER		OFF DUTY	
CRIME RELATED INCIDENTS			
PRIORITISATION BY LINE & OHS USING THE MATRIX  Matrix.pdf			

NAME OF PERSON INVOLVED	
UNIQUE NUMBER OR IDENTITY NUMBER	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

NATURE OF INJURIES SUSTAINED	
UNIT/SECTION/DEPARTMENT	
DATE OF ACCIDENT/INCIDENT	
LOCATION OF INCIDENT/ACCIDENT	
MANAGER/SUPERVISOR	
TELEPHONE NUMBER	

FULL DESCRIPTION OF ACCIDENT/INCIDENT :

WHAT IMMEDIATE ACTION IS TAKEN TO PREVENT SIMILAR INCIDENT IN FUTURE?

LESSON LEARNT (GENERAL)

IMMEDIATE PRELIMINARY FINDINGS OBSERVED

SUBSTANCE ABUSE TEST DONE	YES		NO	
---------------------------	-----	--	----	--

PART 2 – TO BE COMPLETED FOR PUBLIC / CONTRACTOR / LIVESTOCK ACCIDENTS

LOW HANGING CONDUCTOR / CONDUCTOR ON GROUND		OTHER	
IRRIGATION PIPE INTO LINE			
TELKOM LINE INTO ESKOM LINE			
EXTERNAL / SUB-CONTRACTOR			
UNLAWFUL ENTRY / VANDALISM			
CRANE INTO LINE			
TREE ON LINE			
ESKOM VEHICLE INVOLVED			

PART 3 – TO BE COMPLETED FOR ALL VEHICLE ACCIDENTS

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

ESKOM DRIVER & UNIQUE NUMBER	
ESKOM VEHICLE REGISTRATION NUMBER	
DAMAGES TO ESKOM VEHICLE	
THIRD PARTY REGISTRATION NUMBER	
DRIVER OF 3 RD PARTY VEHICLE	
TELEPHONE NUMBER OF 3 RD PARTY	
NAME OF WITNESS	
WITNESS TELEPHONE NUMBER	

PART 4 – TO BE COMPLETED FOR ALL ELECTRICAL CONTACTS

DD OHSET NUMBER	
LINE CLEARANCE	
SUB STATION AND NETWORK	
SECTION BREAKERS	
TEE LINE	
ESKOM VOLTAGE	
BEFORE THE METER	
BEYOND THE METER	

PART 5 – TO BE COMPLETED FOR ALL CRIME RELATED INCIDENTS

NAME OF INVESTIGATING OFFICER	
DATE , TIME REPORTED TO INVESTIGATING OFFICER	
ESTIMATED VALUE INVOLVED	
DESCRIPTION OF PROPERTY DAMAGE	
NAME OF POLICE STATION REPORTED TO	
DATE, TIME REPORTED TO SAPS	
PERSON REPORTING TO SAPS	

PART 6 – TO BE COMPLETED FOR ALL MEDICAL AND LOST TIME INJURIES

NAME OF ATTENDING DOCTOR	
NAME HOSPITAL TAKEN TO	
TELEPHONE NUMBER OF DOCTOR / HOSPITAL	
FAX NUMBER OF DOCTOR / HOSPITAL	
DATE OF TREATMENT RECEIVED	
TIME OF TREATMENT RECEIVED	

PART 7 – TO BE COMPLETED FOR ALL INCIDENTS / ACCIDENTS

FULL NAME OF PERSON REPORTING INCIDENT	
NAME OF SAFETY REP REPORTED TO	
TELEPHONE NUMBER	
FAX NUMBER	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

DATE OF REPORTING INCIDENT / ACCIDENT	
TIME OF INCIDENT / ACCIDENT	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 2 – Transportation of people at the back of open vehicles

DISTRIBUTION TECHNICAL INSTRUCTION

15 December 2011 Enquiries: Moniwa Mahlangu
Tel: (012) 421 6625

TECHNICAL INSTRUCTION: 11TI-027

ART: 21 – RISK MANAGEMENT

TRANSPORTATION OF PEOPLE AT THE BACK OF OPEN VEHICLES (BAKKIES)

Background

In the past years we have experienced fatalities where people were being transported at the back of open vehicles, this has had a major impact since these vehicles are not meant for the conveyance of people but material and tools instead and furthermore it is against existing laws in the country. It was also communicated through a technical instruction (10TI-012) issued on 26 March 2010 that the practice should be stopped, it was however observed that this practice still persists in the organization.

It is further expressed that all Eskom employees and contractors should ensure Zero Harm to employees whilst performing work and even travelling on a daily basis.

Instruction

In order to prevent these incidents and similar consequences, it is decided that no person will be transported in a vehicle that is not intended for the conveyance of people at all times. Therefore no one will be transported at the back of an LDV regardless of whether it is covered with a canopy.

This instruction should be implemented with immediate effect and be communicated to all the relevant parties.

This Technical Instruction is in accordance with Eskom's Policies & Procedure and applicable legislation.

Your commitment to Zero Harm to all is appreciated.


APPROVED BY:

23/12/2011
DATE:

A Noah
Chairperson – Distribution SHEQ Committee

ESKOM COPYRIGHT PROTECTED



Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

ANNEXURE 3 - TRAINING NEEDS MATRIX

	CORE SAFETY, HEALTH AND ENVIRONMENT COMPETENCY TRAINING MATRIX	Template Identifier	240-43921898	Rev	4
		Document Identifier	240-89306315	Rev	1
		Authorisation Date	December 2019		
		Review Date	December 2024		

Introduction:

This training matrix is to be read in conjunction with 32-477 (OHS Training and Development Procedure)

OU/BU		18	10	19	23	23	23	23	23	22	23	23	23	2	22	23	23	23	23	2
														3						3
GM/PSM		4	1	1	0	0	0	0	0	1	0	0	0	0	1	0	0	0	0	0
Required Training		22	11	20	23	23	23	23	23	23	23	23	23	2	23	23	23	23	23	2
														3						3
Training Compliance	99.0%	81.8%	90.9	95.0	100.0	100.0	100.0	100.0%	100.0	95.7%	100.0	100.0%	100.0	100.0	95.7%	100.0	100.0	100.0	100.0	100.0

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

				%	%	%	%	%		%		%		%	%		%	%	%	%	%
EMPLOYEE (Name and surname)	DESIGNATION	Safety Induction Training		OHS Systems Training				General Health and safety				Construction OHS Management Training			Other OHS Training Requirements:						
		Site Specific OHS Induction	Task Specific OHS Induction	ISO 14001 Environmental management system standard awareness	Occupational Health and Safety Assessment Series Awareness – OHSAS 18001: 2007	Occupational Health and Safety Assessment Series Implementation– OHSAS 18001: 2007	ISO 45001 Occupational Health and Safety Standard Awareness	General Health and Safety Awareness/ Introduction to Basic	Office Health and Safety	NEBOSH Occupational Health and Safety	OHS Training for Supervisors	Contracts Health and Safety Management Training for Tender	Contracts Health and Safety Management Training for Procurement	Contracts Health and Safety Management Training for Construction Clerk-of-works, Project Supervisors, Managers	First Aid	Fire Fighting	Safety representative	FAS and FAS Rescue	Fall Protection Planner	ETC.	
		Done	Req	Req	Done	Done	Done	Done	Done	Req	Done	Done	Done	Done	Req	Done	Done	Done	Done	Done	
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	
			Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	
		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	
		Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

**OHS SPECIFICATION**

Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.

Template Identifier	240-73416879	Rev	2
Document Identifier	High/ Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2026		

ON-SITE RISK ASSESSMENT / WORKERS REGISTER
(Informative)

Note 1: Ensure compliance with the minimum requirements as set out in this document.
Information may be added, not removed.

Note 2: This Annexure B form only applies to the non-live work environment.

A: Declaration

Scope of Work:	
Work/Task Order Number:	Work Permit Number: NOTE: Where applicable
Task Manual(s) Number(s): NOTE: Where applicable	

B: Risk Assessment

NOTE: Expand this list as may be necessary.

Identified Hazards	Associated Risks	Steps To be Taken to Minimise the Risk

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.



OHS SPECIFICATION

Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.

Template Identifier	240-73416879	Rev	2
Document Identifier	High/ Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2026		

C: Workers Register

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system. No part of this document may be reproduced in any manner or form by third parties without the written consent of Eskom Holdings SOC Ltd, © copyright Eskom Holdings SOC Ltd, Reg No 2002/015527/30

Page 1 of 3

File name: 559-164864535 Annexure B On-site Risk assessment/Workers Register

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

**OHS SPECIFICATION**

Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.

Template Identifier	240-73416879	Rev	2
Document Identifier	High/ Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2026		



Distribution
Annexure B
On-site Risk Assessment /
Workers Register

Document Identifier	559-164864535	Rev	1
Effective Date	July 2025		
Review Date	June 2028		

The above hazards and the steps taken to minimise the risks have been explained to me. We confirm our participation in the risk assessment and commit to ongoing and continuous risk assessment.

Name (print)	Unique Number	Role	Sign On / Working	Sign off / Withdrawn

D: Declaration

I hereby confirm that the Scope of Work, all necessary precautions, special conditions, hazards involved and the Procedure for Employees' Right of Refusal to Work in an Unsafe Condition Procedure have been explained to, and are understood by, all team members as registered below.

TEAM LEADER PRINT NAME:

SIGNED:

UNIQUE NUMBER:

DATE:

E: Withdrawal

I confirm that all workers involved in the above-mentioned work have been withdrawn, informed that it is no longer safe to work and that the permit to work will be cleared and a debriefing session held.

PRINT NAME AUTHORISED/RESPONSIBLE PERSON	SIGNATURE	DATE	TIME
---	-----------	------	------

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.



OHS SPECIFICATION

Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.

Template Identifier	240-73416879	Rev	2
Document Identifier	High/ Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2026		

F: Debriefing

PRINT NAME AUTHORISED/RESPONSIBLE PERSON	SIGNATURE	DATE	TIME
---	-----------	------	------

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

File name: 559-164864535 Annexure B On-site Risk assessment/Workers Register

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 4 – Construction Evaluation Template

Codes	Legal Requirements	Legal Ref	STATUS			What to look for??	Actions & Comments
			Y	N	N/A		
A1	OHS Policy	Sec. 07 OHS ACT				Written OHS policy wrt protection of the Health and Safety of employee at work Includes description of organisation, Arrangements for carrying out and reviewing policy SHE Policy must be signed by the CEO of the company and dated.	
A2	Mandatory Agreement	Sec. 37(2)				A signed 37-2 agreement (new) by Client and Principal Contractor	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						https://hyperwave.eskom.co.za/240-77037682	
						If applicable between Principal contractor and their appointed contractors (includes security contractors)	
		Section 10 (4)				Is there an agreement of Client and/ or Supplier using third party equipment/ machinery on site?	
		32-726 (Annexure B)				Signed Annexure B Acknowledgement of Eskom SHE rules and other requirements  Acknowledgement Form for Eskom SHE I	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

		Adherence to Requirements				Signed Adherence to the Occupational Health and Safety Act, Act No 85 of 1993 and Regulations, Eskom SHE Specification and other Requirements  Letter to Contractor Executives 18-12-202	
A3.1	Construction Work Permit OR Notification of Construction Work	CR 3(6)				Annexure 1- Proof of Construction Work Permit from Department of Employment and Labour Note: Construction work exceed 365 days, 3600 person days of construction work or works contract is of a value equal to R60 mill (CIDB Lvl 7)	
A3.2		CR 4(1)				Completed & Signed Annexure 2 (by both parties). Proof of stamped	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						Annexure 2 from Department of Employment and Labour Note: Construction work includes demolition of a structure, excavation work, working at a height where there is a risk of falling, Use of explosives	
A4	H&S specification for the project	CR 5(1)(f)				Client Issued H&S Specification to be included in file	
A5	Total Number of employees on site	CR 5(1)(h)				Employee list site specific to the project OHS Organogram with job descriptions	
A6	Letter of Good Standing	CR 5(1)(j)				A valid current FEM/COID letter of Good Standing, Number and expiry date/ Nature of Business must reflect the scope of work of that specific project.	
A7	H&S Plan	CR7 (1)(a)				H&S Plan to be aligned to Clients H&S Specification/ scope specific to the project	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Codes	Appointments & Competencies	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
B1	CEO	Sec.16(1)				Confirmation letter/ Letter of resolution by board of directors	
B2	CEO Assignee	Sec. 16(2)				Letter of Appointment	
B3	H&S Rep.	Sec. 17				Letter of appointment and proof of competency Proof that training service providers is SAQA & QCTO accredited – Scope of approval of accreditation	
B4	H&S Committee Members	Sec. 19(3)				Letters of appointment(Chairperson appointment, Management appointees as well as employee representatives)	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

B5	First Aider	GSR 3(4)				Letter of appointment and proof of competency Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation	
B6	Ladder Inspector	GSR 13A				Letter of Appointment & proof of competence Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation	
B7	Incident Investigator	GAR 9(2)				Letter of appointment and a certificate in incident investigation e.g. RCAT Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

B8	Appointment of Principal Contractor	CR 5(1) (k)				Letter of Appointment of Principal Contractor and competency	
B9	Construction Manager	CR (8) (1)				Letter of Appointment, proof of SACPCMP registration (No candidate registration)	
B10	Assistant Construction Manager	CR (8) (2)				Letter of Appointment, proof of SACPCMP registration (No candidate registration)	
B11	Construction H&S Officer (Full or part-time)	CR 8(5)				Letter of Appointment & SACPCMP Registration	
B12	Construction Work Supervisor	CR 8(7)				Letter of Appointment & proof of competence Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation Line construction competence	
B13	Assistant Constr. Work Supervisor	CR 8(8)				Letter of Appointment & proof of competence	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						Proof that training service providers is SAQA accredited – Scope of approval of accreditation	
B14	Risk Assessor	CR 9(1)				Letter of appointment & proof of formal Risk Assessment course/training attended- Institution name Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation	
B15	Fall Protection Planner	CR -10(1)(a)				Letter of appointment and proof of training Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation US:229994 must reflect on certificate	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

B16	Temporary Work Supervisor	CR 12(2)				Letter of appointment and proof of competency	
B17	Crane supervisor (Tower Cranes)	CR22(a)				Letter of appointment and proof of competency	
B18	Training of Lifting Machine operator	DMR 18(11)				TETA accredited certificate, Certificates & permit to operate, Licences and Prdp's Proof that training service providers is SAQA QCTO accredited – Scope of approval of accreditation Competency certificate must indicate lifting machine code and attachment, Issue date and expiry date	
B19	Construction Vehicle & Mobile Plant operator	CR 23(1)(d)(i)				Letter of appointment and course certificates/ Nationals driver licence (Check road worthiness of the construction vehicles on	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						site) TLB's, Drill rigs, Truck Mounted Cranes, MEWP's and LDV's Proof that training service provider is SAQA QCTO accredited – Scope of approval of accreditation	
B20	Temporal Electrical Installation Inspector	CR24(d)				Letter of appointment and proof of competency Wiremans Licence	
B21	Electrical Machinery Inspector	CR 24(e)				Letter of appointment and proof of competency, Electrical Trade test	
B22	Procedure for prevention of Fall into water & rescue plan of persons in danger of drowning	CR26(1)(a)				Procedure & Rescue Plan	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

B23	Stacking & Storage	CR 28(a)				Letter of Appointment & proof of competence – Formal training certificate	
B24	Fire Equipment Inspector	CR29 (h)				Letter of appointment and proof of competency Basic fire fighting training	
B25	Mobile Elevated Working platforms, Skyjacks: Operating certificates on file	DMR18(11) SANS 1887:2007				TETA accredited certificate, Certificates & permit to operate, Licences and Prdp's Proof that training service providers is SAQA or QCTO accredited – Scope of approval of accreditation Competency certificate must indicate lifting machine code and attachment, Issue date and expiry date	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

B26	Inspector of Lifting Machines &Tackle	DMR- 18 (5)				Proof of competency: LMI: Proof of accreditation number (ECSA/LEEASA) LME: Proof of registration with Dept of Labour, Scope of approval	
B27	Load Test certificate	DMR- 18 (5)				Load Test certificate for Lifting machines and hand held powered lifting devices(lever hoists)Safe working load at 110% to be tested	
B28	HCA Controller	HCA Regulations				Letter of appointment and proof of competence for Hazardous chemicals (Valid PCO for Vegetation Management)	
B29	Excavation Supervisor	CR13				Appointment and Competence	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						Proof that training service providers is SAQA or QCTO accredited – Scope of approval of accreditation	
B30	Demolition Supervisor	CR14(1)				Letter of appointment and proof of competency Proof that training service providers is SAQA or QCTO accredited – Scope of approval of accreditation Line construction training Authorisation Eskom Training for constructing , Maintain and Dismantle overhead power Lines is – •The MV line Constructions Training 11KV up to 33KV which is ELW 01 to ELW10.	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						<ul style="list-style-type: none"> •Low Voltage - LV Line contractions ELW 11 to ELW 12. •The 5 pole structure training for 66KV to 132KV. 	
Codes	Risk Assessment	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
C1	Risk and Hazard Identification	CR 9(1)(a)				Site specific Baseline Risk Assessment	
C2	Risk and Hazard Analysis	CR 9(1)(b)				A documented method on how hazards and risks are evaluated and analysed : Risk matrix	
C3	Risk Control	CR 9(1)(c)				Documented Risk Mitigation/ Control plan	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

C4	Task Manuals and Safe Work Procedures	CR 9(1)(c)				List safe work procedures to mitigate, reduce or control the risks on the BRA Methods used to address all the risks identified per location and as per scope of work	
C5	Monitoring Plan/Mechanism	CR 9(1)(d)				A monitoring plan- How are risks monitored. Note: during execution phase planned task observation at 4 per month by the supervisor, Working at Heights & Specialized Vehicle equipment	
C6	Review Plan	CR9(1)(e)				A review plan demonstrating the frequency of review of Baseline RA's (Date of review of the plan if terms of incident occurs)	
Codes	Fall Protection	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

D1	Fall Protection Plan: Risk assessment	CR 10(2) CR 10(2) (a)				Proof of: a risks assessment that includes Hazards and risks associated with all work carried out at positions of elevation and procedures and methods used to address all the risks identified per location.	
D2		32-418				Risks to be considered refer to 3.3.2 (b) pg. 8&9 of 32-418: Working at Heights Procedure.  Work at Height Standard 32-418.pdf	
D3	Fall Protection plan: Process for evaluating employees medical fitness necessary to work in a fall risk position	CR 10(2)(b)				Process for evaluating employees medical fitness	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

D4	Fall protection plan: Training programme	CR 10(2)(c)				Programme for training of employees working from a fall risk position	
D5	Fall protection plan: Training programme					FAS Unit standard 229998	
						Rescue Training Unit standard 229995	
D6	Fall protection plan: Inspection, testing and maintenance of all Fall Protection Equipment	CR10(2)(d)				Procedure outlining the Inspection, testing and maintenance of all Fall Protection Equipment	
D7	Fall protection plan: Rescue Plan	CR10(2)(e)				Rescue plan detailing the necessary procedure, personnel and suitable equipment required to affect rescue of a person in the event of a fall incident to ensure that the rescue procedure is implemented immediately following the incident	
D8	3.5.11 At least two persons per team have to be able to perform	32-418				Two rescuers per team – Provide names of rescuers	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

	rescues if work at height is involved. All personnel trained to perform rescues will be trained to first aid Level 2.					Proof of first aid level two training of rescuers	
Codes	Induction Training	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
E1	Training Matrix/ Syllabus of the Company					Training analysis/Matrix	
E2	Proof of Eskom's Induction Training on file.					Proof of Eskom Induction conducted	
E3	Was Induction done by the Company?					Proof of Company Induction (Attendance register) & Contractor Induction Curriculum Content	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Codes	Medical Surveillance	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
F1	Crane operator's medical certificate of fitness	CR 22(f)				Medical Fitness certificates by OHP & OHNP	
F2	Construction Vehicle & Mobile Plant Operator's medical certificate of Fitness	CR 23(1)(d)(ii)				Medical Fitness Certificate by OHP & OHNP	
F3	Medical certificates for all employees	CR 7(8)				Medical Certificates of all employees in the project by OHP & OHNP	
F4	Certificate of medical fitness	CR10(2)(b)				Evaluation of medical fitness of employees working at heights by OHP & OHNP	
Codes	Dismantling of structures	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

G1	Task Manuals and Safe Work Procedures	240-147749433				<p>Procedure for testing integrity /Rotten of structures?</p> <p>Will work be performed on poles not being classed. Yes/No</p> <p>Contractor to indicate how they will ensure compliance to below Eskom standards / Procedures / Instructions:</p> <p>Working on Suspect and or Unclassified poles engineering instruction</p> <div data-bbox="1283 775 1335 836" data-label="Image"> </div> <p>Working on Suspect or Unclassified Poles :</p> <p>Classes poles: how will testing be done?</p>	
----	---------------------------------------	---------------	--	--	--	--	--

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

		CR 11 & CR 14 (2)				Contractor to indicate how they will ensure compliance to Legal requirements and below Eskom standards / Procedures / Instructions - Safe Work Procedures for dismantling of structures, Procedure to prevent the uncontrolled collapse of new or existing Structure, Method statement on procedure to be followed in demolishing structure	
		240-153633907				REPLACING OF A 5-POLE SUSPENSION STRUCTURE WOOD POLE	
		240-97759836				 Replacing of a 5-Pole Suspension Structure.	
						MANUAL REPLACEMENT OF A ROTTEN / DAMAGED WOODEN POLE STRUCTURE	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

		240-97759751			 Manual Replacement of a Rotten-Wooden F Replacement of a Rotten wooden pole with a vehicle mounted crane  240-97759751 Replacement of a Rot	
G2	Task specific Risk Assessment for Dismantling of structures	CR 9(1)(a)(e)			Proof of: a risks assessment that includes Hazards and risks associated with all work carried out at positions of elevation and procedures and methods used to address all the risks identified per location and as per scope of work	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

G3	Engineering surveys results/Reports	CR14(2)				Results of Engineering surveys conducted, Entity/ Service provider competence who conducted the survey report and confirmation. Contractor to have the results of the surveys reports that was done. Eskom representative to confirm/contractual approval for the survey contractor	
G4	Structural integrity check	CR 14 (3)				Inspection checklist	
Codes	Asbestos	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
H1	Identification of asbestos in place	AAR 3				Employer to provide proof that all asbestos containing material at the workplace is identified by a competent person	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

H2	Inventory of asbestos in place	AAR 4				Employer must obtain the services of a competent person to ensure that all materials identified to be asbestos containing material are entered in an inventory of asbestos in place which is kept at the workplace or premises	
						Inventory of asbestos in place must contain the following information: Date on which material was identified A description of the material, quantity and extent of deterioration Location as detailed on a floor plan Confirmation of labelling and signage as required by AAR 20	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						Risk categorisation derived from the asbestos risk assessment as detailed in AAR 5(3) A description of potential exposure scenarios as required by AAR 6(2)(b)	
						Inventory revised by competent person at intervals not exceeding 24 months	
						Asbestos Client must ensure that a copy of the asbestos inventory is given to the Mandatory, registered asbestos contractor, Approved Inspection Authority (AIA) before asbestos removal or repair work commences	
H3	Asbestos Risk assessment	AAR 5				Is an asbestos risk assessment in place	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

H4	Asbestos management plan	AAR 6				<p>Provide proof that a competent person has prepared a written asbestos management plan and that it includes the following:</p> <p>A procedure that contains at least measures related to: Implementation of AAR 3, 4,5,8 and 20; Repair removal and management of asbestos containing material;</p> <p>A procedure for following scenarios: Incidents; Emergencies; Removal work; Repair work</p>	
H5	Information, Instruction, and training	AAR 7				<p>Are supervisors and employees adequately and comprehensively informed, Instructed and trained by a competent person. Provide proof of training records</p>	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

H6	Notification of asbestos work	AAR 10				Provide proof that Chief Director: Provincial Operations has been informed in writing 7 days prior commencement of asbestos work	
H7	Duties of Asbestos Client for asbestos work	AAR 11 (1) (a-d)				Type 1 asbestos work provide: Up to date inventory of asbestos in place as per AAR 4 when asbestos work is planned Ensure that Asbestos risk assessment is carried out prior to asbestos work is done as per AAR 5 Ensure written Safe work procedure is developed and followed Provide adequate Information, Instruction and Training as per AAR 7 to ant person who may be exposed to asbestos as a result of asbestos work	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

		AAR 11 (2) (a-j)				<p>Type 2 & 3 asbestos work provide:</p> <p>Up to date inventory of asbestos in place as per AAR 4 when asbestos work is planned, If not identified on inventory review and update inventory</p> <p>Ensure that Asbestos risk assessment is carried out prior to asbestos work is done as per AAR 5</p> <p>Appoint in writing and Approved Inspection Authority (AIA)</p> <p>Ensure that appropriately registered asbestos contractor performs Type 2 &3 work as per Asbestos plan of work</p> <p>Ensure that Notification of asbestos work is done as per AAR 10(2)</p>	
--	--	------------------	--	--	--	--	--

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						<p>Co sign asbestos plan of work for asbestos repair and removal</p> <p>Stop any registered asbestos contractor from executing any asbestos work which poses a risk to health and safety</p> <p>Ensure registered asbestos contractor is registered and in good standing with Compensation fund or licenced compensation insurer</p>	
		AAR 11 (3)				<p>After completion of Type 2&3 asbestos work, asbestos client must obtain and asbestos clearance certificate from the approved inspection authority</p>	
H8	Duties of registered asbestos contractor for asbestos work	AAR 12 (1)				Type 2&3 asbestos work registered asbestos contractor :	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						<p>Undertake only the type of asbestos work for which contractor is registered</p> <p>Appoint OHS representative as per Section 17</p> <p>Obtain up to date inventory from of asbestos in place from asbestos client prior to asbestos work taking place</p>	
		AAR 12 (2)				<p>Before and during asbestos work ensure that a risk assessment is performed that includes identification of hazards to which persons are exposed to; an assessment of the risks related to hazards and documented control measures in place</p> <p>Risk assessment is reviewed at regular intervals, when an incident occurs, when</p>	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

					scope of work changes. Up to date copy of risk assessment must be available on site	
		AAR 12(3) (a)			Provide proof that Chief Director: Provincial Operations has been informed in writing 7 days prior commencement of asbestos work	
		AAR 12(3) (b)			Appoint in of an asbestos removal supervisor for asbestos work site Asbestos supervisor must ensure : OHS compliance on site; compliance with safe asbestos removal or repair procedures; correct use of PPE; proper decontamination and waste disposal	
		AAR 12(3) (f)			Ensure that and Approved Inspection Authority has been appointed in writing by the asbestos client	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

H9	Duties of an approved inspection authority (AIA) for asbestos work	AAR 13				<p>AIA involved in Type 2 & 3 work must:</p> <p>Ensure appropriately registered asbestos contractor performs only type 2 and 3 asbestos work</p> <p>Obtain a copy of up to date inventory of asbestos from asbestos client prior to asbestos work taking place</p> <p>Compile plan of work in consultation with registered asbestos contractor as per AAR 15</p> <p>Approve and submit plan of work to Chief Director</p> <p>Perform planned asbestos air monitoring in accordance with AAR 16 and provide results to asbestos contractor and client</p>	
----	--	--------	--	--	--	--	--

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						Issue asbestos report with findings and recommendations Upon completion of Type 2 & 3 asbestos work clearance is performed as per AAR 22	
H10	Plan of work	AAR 15				Written plan of work must contain: (a) Name, contact details and responsibilities of the registered asbestos contractor, approved inspection authority, asbestos waste transporter, asbestos waste disposal site and asbestos client, where applicable; (b) name and contact details of the asbestos removal supervisor for the asbestos work site; (c) details of the asbestos to be removed, including the location, type, estimated quantity and condition of the asbestos; (d) a list of employees' names and identification numbers with verification of valid asbestos training and medical	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						surveillance records for the asbestos work site; (e) expected commencement and completion dates; (f) air monitoring method used, and frequency of air monitoring, in accordance with regulation 16; (g) details of how the asbestos removal work will take place, including methods of removal, tools and equipment, and the appropriate personal protective equipment to be used; (h) details relating to the requirements of decontamination facilities and decontamination procedures; (i) details of demarcation, labelling and signage requirements for regulated asbestos areas, asbestos waste and temporary on-site storage areas; (j) procedure for decontamination of the work area, tools and equipment; (k) emergency procedures in the event of uncontrolled asbestos release; (l) method for disposal of asbestos waste;	
--	--	--	--	--	--	--	--

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						(m) detail of asbestos clearance certification; and (n) specific relevant prohibitions. Plan of work must be signed by asbestos Client, asbestos contractor and AIA , accepting their duties	
H11	Air monitoring	AAR 16				Type 2&3 asbestos work asbestos client must ensure that air monitoring is done Environmental air monitoring done by AIA	
H12	Medical surveillance	AAR 17				Provide proof of valid medicals done by Occupational Medical Practitioner	
H13	Regulate asbestos area	AAR 18				Demarcate and identify asbestos area	
H14	Personal Protective Equipment (PPE) and facilities	AAR 19				PPE matrix indicating PPE required for Asbestos work	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

					Provide information, instruction, training and supervision as required for use of PPE Provide process detailing cleaning, decontamination, storage facilities for personal protective equipment	
H15	Labelling and signage	AAR 20			Identify asbestos in place using the pictogram as per Annexure 1 Clearly label all asbestos waste as per AAR 20 (a-c)	
H16	Disposal of asbestos	AAR 21			Employer must ensure: (a) all asbestos waste is placed in containers that will prevent exposure during handling;	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						(b) the premises, structure or area are thoroughly checked to ensure that all asbestos waste intended for disposal has been removed; (c) all vehicles, reusable containers or any other similar articles, which have been in contact with asbestos waste, are cleaned and decontaminated after use in such a way that such vehicles, containers or similar articles do not cause a hazard inside or outside the workplace concerned; (d) a document is obtained from the asbestos disposal site, contemplated in subregulation (e), for all asbestos waste removed from the workplace; all asbestos waste is disposed of only on sites specifically designated for this purpose in terms of the Environment Conservation Act, 1989, and the National Environmental Management: Waste Act, 2008; (e) all persons involved in the collection, transport and disposal of asbestos waste, who may be exposed to that waste, are	
--	--	--	--	--	--	--	--

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

						provided with suitable personal protective equipment; (f) the drivers of vehicles carrying asbestos waste are provided with written instructions on safety precautions and emergency procedures; and (g) where the services of a contractor for the transport and disposal of asbestos waste are used, the contractor complies with the provisions of these Regulations.	
H17	Asbestos Clearance certificate	AAR 22				Following the completion of type 2 or type 3 asbestos work, an approved inspection authority must— (a) conduct a thorough visual inspection of the relevant work area; (b) conduct air sampling to ensure compliance with the clearance indicator; (c) ensure that all asbestos waste has been removed in accordance with the requirements of regulation 21; and (d) issue a written declaration for the purpose of clearance certification.	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Codes	Procedures	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
I1	Incident Management Procedure	32-95				Incident Management procedure to be aligned to 32-95, wrt reporting, recording, classification and investigation	
I2	Effective Evacuation Plan	CR 29(1)(i)				Evacuation Plan (e.g. Check emergency number, appointments letters and Fire extinguisher handling awareness etc.)	
I3	Vehicle Safety Management	32-345				Vehicle Safety Management Procedure to be aligned to Eskom 32-345	
I4	Procedure for prevention of Fall into water & rescue plan of persons in danger of drowning	CR26(1)(a)				Procedure & Rescue Plan	
Codes	ORHVS	Legal Ref	Status			What to look for?	Actions & Comments

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

			Y	N	N/A		
J	Copies of Valid ORHVS certificates and Authorizations if work is to be done in any Eskom HV yard, substation or servitude authorized by the GMR 2(1)					Copies of valid ORHVS certificates and Authorisations	
Codes	Principal Contractor to inform the client regarding use of contractors	Legal Ref	Status			What to look for?	Actions & Comments
			Y	N	N/A		
K1	Is the Principal Contractor using contractors?	32-136				List of contractors	
K2	Is the contractor's H&S Plan approved by the Principal Contractor (Client)					Copy of contractor's H&S plan , signed by the Principal Contractor	
Other SHE Specification Requirements							

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

% Compliance to SHE Specification	100% compliant			Below 100% compliant
Function Representative	Name & Surname	Signature	Date	
Signature of Eskom SHE Officer				
Signature of Project Co-ordinator				
Signature of Principal Contractor Health and Safety Officer / Representative				

(100% requirements met) - The file is FULLY compliant in all respects and the contractor may access the site and commence work.

(Less than 100% requirements met) - The file is non-compliant – The contractor may not have access to site or commence work. The contractor must rectify the deviations as listed on the following page and the file is re-viewed and a new assessment form is completed achieving full compliant.

(100% requirements met) - The file is FULLY compliant in all respects and the contractor may access the site and commence work.

(Less than 100% requirements met) - The file is non-compliant – The contractor may not have access to site or commence work. The contractor must rectify the deviations as listed on the following page and the file is re-viewed and a new assessment form is completed achieving full compliant.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 5 – 37(2) Agreement Template

	Occupational Health and Safety Act: Section 37(2) Agreement - Form	Template Identifier	240-43921804	Rev	5
		Document Identifier	240-77037682	Rev	6
		Effective Date	December 2020		
		Review Date	December 2025		

SECTION 37(2) AGREEMENT CONCLUDED BETWEEN

.....[insert name of subsidiary or Eskom Holdings SOC Limited]

AND

.....

(Name of contractor/supplier)

I,[(insert name of person representing contractor/supplier company)]representing [insert name of contractor/supplier], do hereby acknowledge that [insert name of contractor/supplier] is an employer in his/her own right, with duties as prescribed in the Occupational Health and Safety Act No. 85 of 1993 ("the Act"), as amended, and agree to ensure that all work will be performed and/or machinery or plant used in accordance with the provisions of the Act.

I undertake that [insert name of contractor/supplier] shall strictly adhere to, and ensure that his/her employees adhere to, the provisions of the Occupational Health and Safety Act, 1993 (Act 85 of 1993).

I have been provided with OHS specifications for project/service[insert brief details of project/service, for example, name, contract/project number] and will comply with the requirements set out in these.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Occupational Health and Safety Act: Section 37(2) Agreement - Form	Document Identifier	240-77037682	Rev	6
--	---------------------	--------------	-----	---

I accept and agree that the OHS specifications constitute arrangements and procedures between (*insert name of contractor/supplier*) and [*insert name of subsidiary or Eskom Holdings SOC Limited*] which will ensure compliance by [*insert name of contractor/supplier*] with the provisions of the Act, as contemplated in section 37(2) of the Act.

This agreement constitutes the sole agreement between the parties, and no variation, modification, or waiver of any of the provisions of this agreement or consent to any departure from these shall, in any manner, be of any force or effect, unless confirmed in writing and signed by both parties, and such variation, modification, waiver, or consent shall be effective only in the specific instance and for the specific purpose and to the extent for which it was made or given.

This agreement is signed on behalf of the parties, each signatory to this warranting that he/OHS has the requisite authority to do so.

Signed this day of 20 at

..... (*Place*)

(*Full name*)..... (*Signature*)on

behalf of (**Contractor/supplier**)

Contractor Responsible Manager (*responsible for signing the contract on behalf of the contractor/supplier*)

Witnesses

1.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Occupational Health and Safety Act: Section 37(2) Agreement - Form	Document Identifier	240-77037682	Rev	6
--	---------------------	--------------	-----	---

2.

Signed this day of 20 at (*Place*)

(*Full name*..... (*Signature*) on

behalf of [insert name of subsidiary or Eskom Holdings SOC Limited]
(Contracts and/or Project Manager or Representative)

Witnesses

1.

2.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 6 - Principal Contractor 5(1)(k) Template Check for latest revision

	Principal Contractor 5(1)(k) Construction Regulations 2014 Appointment Letter	Document Identifier	240-64729708	Rev	7
		Effective Date	Aug 2021		
		Review Date	September 2026		

I, **(Name & Surname of the appointer)** the **(Designation of the appointer*)** for **(Site name)** hereby appoint you **(Add Appointee Name & Surname)** being the Contractor's Representative for **(Add full company Name)** as **Principal Contractor** for **(Scope of work)** as per Construction Regulations 2014, Regulation 5(1)(k); to perform the following duties as prescribed by Construction Regulations 2014, Regulation 7(1) ; .

Designated Functional Responsibilities and Authority

In particular you are required amongst others, to ensure the following –

- provide and demonstrate to the client sufficient documented Health and Safety Plan based on clients documented health and safety specification contemplated in regulation 5(1)b of CR 2014
- open and keep on site a health and safety file, which must include all documentation required in terms of the Act, which must be available on request to an inspector; the client, the client agent or a contractor;
- on appointing of any other contractor and ensure compliance with the provision of the Act as contemplated on regulation 7(1)c;
- ensure health and safety plan contemplated in regulation 7(1)(a) as well as contractors health and safety plan is available on request to an employee, inspector, a contractor ; the client or client's agent
- hand over a consolidated health and safety file to the client upon completion of the construction work;
- include and make available a comprehensive and updated list of all contractors on site accountable to the principal contractor, the agreements between the parties and the type of work being done
- ensure that all his or her employees have a valid medical certificate of fitness specific to the construction work to be performed and issued by an occupational health practitioner in the form of Annexure 3.
- stop any contractor from performing a construction activity which poses a threat to the health and safety of persons and which is not in accordance with the client's health and safety specifications and the Contractor's Health and Safety Plan for the site.

You are required to report any deviations from the above-mentioned instructions to me.

You shall submit a written weekly report on all shortfalls that have not been met in terms of these regulations.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

This appointment is effective from **(Add Start Date Here)** until withdrawn by the **(Designation of the appointer*)**.

Signature
(Designation of the appointer*)

Date

Acceptance of Designation

I, **(Add Appointee Name Here) (Add Unique number or ID number)**, hereby acknowledge and accept the above-mentioned appointment and declare that I am conversant with the relevant provisions of the Occupational Health and Safety Act No. 85 of 1993.

Principal Contractor CR 5 (1)(k)

Date

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 7 – Annexure B: Eskom Acknowledgement Form for OHS legal and other requirements

	Annexure B: Eskom Acknowledgement Form for OHS legal and other requirements	Template Identifier	240-43921804	Rev	5
		Document Identifier	240-77471499	Rev	3
		Effective Date	May 2021		

Annexure B: Acknowledgement Form for Eskom OHS legal and other requirements

NOTE: the supplier/contractor/tenderer has to ensure that he/OHS understands the OHS requirements listed hereunder.

1. The supplier/contractor/tenderer is expected to comply to the following documents when working at/rendering a service to Eskom but not limited to the following: <ul style="list-style-type: none"> a. Eskom contractor Health and Safety requirements standards 32-136 b. OHS specification/requirements provided c. Occupational Health and Safety Act 85 of 1993 d. Compensation for Occupational Diseases and Illnesses Act 130 of 1993 <p>Note: Please note that after contract award, it is your responsibility to fully align the company's processes to Eskom's OHS requirements (policies, procedures, standards etc).</p>
2. Penalties shall be enforced on the main supplier for non-conformance/s (identified for the main supplier and/or its contractor and/or supplier) pertaining to Eskom and/or Statutory OHS requirement/s.
4. Ensure that all employees (contractors/suppliers) undergo the relevant Eskom induction and the company's
5. Management of Contractors/ Suppliers The main contractor/supplier: <ul style="list-style-type: none"> a) Has to demonstrate to Eskom the process and selection criteria applied when appointing contractors and suppliers. b) Has to provide notification to Eskom, prior to the appointment of contractors or suppliers for the commencement of work. c) Has to ensure that contractors/ suppliers have adequate resources and competencies. d) Is accountable for the management of its contractors/ suppliers in order to ensure that the applicable legal and Eskom requirements (that are applicable to the main supplier during contract execution) are complied with by the contractors or suppliers.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- e) The main supplier shall monitor contractors or suppliers through audits and assessments with regard to OHS compliance during the execution of the work.
- f) The grounds for the termination of work done by contractors/suppliers shall be provided by the main supplier.
- g) All non-conformances/non-compliance by the contractors/suppliers (all tiers) to the main supplier shall be dealt with directly with the main contractor/supplier in terms of performance and penalty processes.
- h) Eskom reserves the right to verify this when deemed necessary. The contractor may be instructed to provide copies of testimonials/references and the contact detail of clients (including Eskom) for whom the Company has done previous work of a similar nature

I, the undersigned, hereby acknowledge that I have obtained copies of the above documents and confirm that I fully understand them and the consequences of non-compliance.

Signed at on day of 20.....

Company/Supplier Name:

Name of Authorised person (CEO/Director/ Managing Director)

.....
Signature

.....
Date

Witness 1

Witness 2

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 8 – Behavioural Observation Form

Behavioural Observation Form - Standard					
Observer's Details					
Name of Observer:			Date of Observation:		
Duration of Observation (min) :			Task Grading of Observer:		
Operation Unit:			Observer's Dept./Area:		
Dept. observed:		Location/Area/PS/Unit:			
People Observed		Group Observed			
Number of people observed:		Employee:		Co-Observers	
Number of people working safely:		Principal Contractor:		Co-Observer:	
		Sub-Contractor:		Co-Observer:	
Number of people working unsafely:		Visitor:		Co-Observer:	
Type of activity Observed:					
Safe behaviours and Safe Conditions Observed					
Activity is:	Safe	(If block is selected - describe safe behaviours and conditions in above block)			
	Unsafe	(If block is selected - Please identify the unsafe actions in the categories below)			
Unsafe Categories					
PPE		Positions of People		Reactions of People	
☐ Ears		☐ Striking against or getting struck by		☐ Adjust PPE	
☐ Eyes and face		☐ Caught in or between objects		☐ Change position	
☐ Feet and Legs		☐ Fall/could fall		☐ Rearrange job	
☐ Hands and Arms		☐ Contacting extreme temperatures		☐ Stop activity	
☐ Head		☐ Inhaling or swallowing hazardous substances		Orderliness/Housekeeping	
☐ Respiratory System		☐ Repetitive motion		☐ Not understood	
☐ Trunk		☐ Awkward positions		☐ Not known	
		☐ Electrical contact		☐ Not followed	
Tools and Equipment		Procedures			
☐ In bad, unsafe condition		☐ Not adequate		☐ Not followed	
☐ Not used correctly		☐ Not known		☐ Not understood	
☐ Wrong for job					
Reasons for Unsafe Behaviours					
☐ Not available		☐ Knowledge (training)			
☐ Unaware of risk		☐ Not practical			
☐ Uncomfortable		☐ Time pressure			
☐ Cost		☐ Unclear responsibility			
☐ Forgetting					
Comments/Follow-up Actions:					

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 9 – Annexure D OHS Post-contract Reviews

	Annexure D: OHS KPI's and Post-Contract Reviews	Template Identifier	240-43921804	Rev	5
		Document Identifier	240-77472561	Rev	3
		Effective Date	May 2021		

The objectives and outcome of the OHS post-contract review shall be reflected in the contractual requirements for the supplier so that the supplier is aware of this exercise.

An evaluation will be conducted and will be supported by the objective evidence documented during the term of the contract. The evaluation report must be filed in the contract documents.

The following criteria (but not limited to) shall be considered for the review:

- Accident and injury data for the contract.
- OHS non-conformances.
- Duration and effectiveness in addressing and closing out OHS deficiencies/corrective actions.
- Legal compliance with OHS requirements.
- Number of behavioural safety observations conducted by contract manager and the contractor supervisors.
- Close-out of Incident Investigations.
- No. of staff members (incl. subcontractors and suppliers) who contravened the Eskom Lifesaving rules.
- Prohibition and contravention notices issued by Department of Labour/Dept. of Mineral Resources notices, Department of Environmental affairs etc.
- Contributions and effort made to improve OHS performance
- Contractor /Supplier (including its contractor) total number of incidents:
 - Fatalities,
 - Lost-time injuries,
 - reportable incidents (Department of Labour/Department of Mineral Resources/Department Environmental affairs)

The following matrix shall be used to assess the performance against the identified criteria.

The OU/BU may add or remove KPI's to ensure practicality:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

	Annexure D: OHS KPI's and Post-Contract Reviews	Template Identifier	240-43921804	Rev	5
		Document Identifier	240-77472561	Rev	3
		Effective Date	May 2021		

1. Contractor OHS KPI (Business units or Operating units must ensure alignment to the business KPI's)

Supplier's name: **Project Ref number:**

Scope of work:

KPA	KPI	Weighting	Floor	Kick	Target	Stretch	Ceiling
1. Fatalities	1.) No of fatalities experienced for the fiscal year or the duration of the project if less than 12 months	40%	2	1	0	-1	-2
2. Lost time incidents / LTIR	1.) Lost time incidents/LTIR for the fiscal year the duration of the project less than 12 months	30%	4	3	2	1	0

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

3. OHS compliance	1.) Supplier average audit rating for the fiscal year the duration of the project less than 12 months	20%	1	2	3	4	5
	2.) Supplier has closed out audit findings/non-conformances within a specified period.		80%	85%	90%	95%	10%
	3.) Eskom Safety rules violation for the fiscal year the duration of the project less than 12 months		40%	20%	0%	-20%	-40%
4. OHS improvement programme	1.) Supplier has implemented OHS interventions or initiatives to improve on the Health and Safety of employees	10%	60%	70%	80%	90%	100%
	2.) Supplier participate in Eskom's OHS interventions and programmes (Safety stand offs, OHS campaigns/events, cooperation, provide the required feedback or information etc)		60%	70%	80%	90%	100%

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Reticulation including the installation of smart meters, re-closers and voltage regulators.	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

	Annexure D: OHS KPI's and Post-Contract Reviews	Template Identifier	240-43921804	Rev	5
		Document Identifier	240-77472561	Rev	3
		Effective Date	May 2021		

2. Post Contract Evaluation Report:

Unacceptable	Satisfactory	Good	Exceptional
Comments:			
Decision: <u>Will this Supplier be Recommended for Future Work Within Eskom? Tick Applicable Column</u>			
Yes, With Reservations	Yes	No	
Substantiate the reasons for reservation (if applicable):			
Names and designations and contact details of persons that conducted the post contract review:			

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 10 – TASK OBSERVATION FORM

1					
.					
	Task observer's name:..... Section / department: Occupation:..... Date: Time with task:		Task observed / Scope of work: Location: Is there a procedure for this task? ☐ Procedure ref. no. Work order no.		
2	REASON FOR OBSERVATION				
.	Planned ☐ Accident repeater ☐ Experience worker ☐ Risk taker ☐ Follow-up ☐ Name of employee/s being observed:				
3	TASK OBSERVATION				
.					
	Did employee adhere to the procedure/practice requirements?		Could observed practices / conditions lead to:		
		Yes No		Yes No	
	1. Failure to use PPE		1. Injury:		
	2. Ignore safety specifications		a) Risk of getting caught by		
	3. Tools equipment:		b) Risk of striking against/get struck by		
	a) used correctly		c) Risk of fall from same level		
	b) In good and safe condition		d) Risk of fall from different level		
	c) Test certificates valid and available		e) Risk of slip, trips and falls		
	4. Toolbox Talk:		2. Illness (fumes, gas, etc.)		
	a) Work instructions/task manuals used		3. Costs (delays)		
	5. Complete Worker's register		4. Poor quality (non-conformance)		
	6. Risk Assessment been done				
	7. Valid work permits available				

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

4	NON COMPLIANCE PRACTICES OBSERVATION					
.						
		Yes	No		Yes	No
	1. Working at unsafe speed			7. Failure to warn		
	2. Using unsafe equipment			8. Taking chances		
	3. Using equipment unsafely			9. Failure to identify hazards		
	4. Unsafe loading, placing & lifting			10. Failure to secure lock-out		
	5. Taking unsafe position			11. Safety signs ignored		
	6. Safety rules ignored					
	NOTE: ALL OBSERVED CLASS HAZARDS SHALL REQUIRE IMMEDIATE INTERVENTION					
5	OBSERVED DEVIATIONS / NON-CONFORMANCES					
.						
6	AT RISK BEHAVIOURS					
.						
7	PROPOSED CONTROLS					
.						
	Compile a procedure for this task	☐		Issue a standing instruction	☐	
	Revise present procedure	☐		Change work methods	☐	
	Retraining of employees	☐		Professional referral	☐	
	Engineering revision	☐		Coaching	☐	
8	ANALYSIS					
.						

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

IAC – inadequate capability ☐	ABU – abuse or misuse / e ☐ / drugs or alcohol	MAIN – inadequate maintenance ☐
KNO – lack of knowledge ☐	NAT – natural factors ☐	EQU – inadequate equipment ☐
SKI – lack of skill ☐	LEA – inadequate leadership ☐	STA – inadequate work / train. Standards ☐
STR – stress ☐	ENG – inadequate engineering ☐	WEA – wear & tear ☐
MOT – improper motivation ☐	PUR – inadequate purchasing ☐	CON – inadequate control ☐

9.	DISCUSSION BETWEEN SUPERVISOR/OBSERVER AND EMPLOYEE	
	1. EMPLOYEE EXPLANATION FOR RISK BEHAVIOUR	
	2. AGREEMENT TO CHANGE AT RISK BEHAVIOUR	
10.	FOLLOW-UP ACTION	WHEN / WHO

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Person being Observed signature: _____ Date: _____

Signature (Task Observer): _____ Date: _____

Signature Chairperson Safety Committee: _____ Date: _____

(if deviations were found)

NOTE 1: ALL PROPOSALS / REVISIONS MUST BE ATTACHED TO THIS REPORT

NOTE 2: THIS FORM SHOULD USED FOR UNPLANNED OBSERVATIONS CARRIED OUT ON NON CRITICAL TASKS

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Annexure 11 – Contractor OHS File Hand Back Record

	CONTRACTOR OHS FILE HAND BACK RECORD	Document Identifier	240-76755865	Rev	1
		Authorisation Date	01 March 2014		
		Review Date	January 2019		

Delete not applicable

*Contract / Project : _____

*Contract / Project Number: _____

I, _____ in my capacity as _____,
have received the OHS File for the above mentioned Contract / Project from:

Details of Contractor

Trading Name	
Company Registration Number	
Contact Person	
Contact Number	
Address	

The contents of the file include:

Note: member receiving to ✓ requirement for inclusion in file for project specific

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

Requirement	Minimum Requirement ✓	In file
All drawings, photographs, designs	✓	
Copy OHS policy	✓	
Copy Letter of Good Standing	✓	
Sect 16(2) Appointment	✓	
Project / Contract scope of work	✓	
Project / Contract OHS plan	✓	
Principal Contractor Appointment	✓	
H & S Representative appointment	✓	
Safety Officer appointment	✓	
Construction Notification application	✓	
Construction Work Permit approval	✓	
Approved copy of specific OHS plan	✓	
Project Organisational Organogram	✓	
Breakdown for costing for OHS	✓	
Scope of Work	✓	
Competency Training records	✓	
Incident investigation records	✓	
Base Line Risk Assessments	✓	
Fall protection plan	✓	
Medical Certificates	✓	
Emergency Management plans	✓	
Fire Risk Management plans	✓	
First Aid Management	✓	
OHS Communication System	✓	
Pre start job assessment / talk	✓	
Relevant Equipment check lists	✓	
Audit reports		
•		
•		
•		
•		
•		
•		
•		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

- Assessor to add additional project / contract specific requirements

Comments by member receiving file:

OHS File handed in by:

Name: _____ Signed: _____

Date of Handover: _____

OHS File received by:

Name: _____ Signed: _____

Date Receiving: _____

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

OHS COSTING

ITEM	DESCRIPTION	Reference	UNIT	QUANTITY (1)	PRICE PER UNIT (2)	TOTAL (1)*(2)
1.	Supply of all items of Personal Protective Clothing/Equipment & ensure use thereof for full compliance					
1.1	Steel toe capped safety boots	General Safety Regulation 2: Personal Safety Equipment and Facilities				
1.2	Appropriate protective clothing					
1.3	Gloves					
1.4	Color coded hardhats [Blue for laborer, Red for First Aider, Green for SHE Reps and White for Supervisors and Managers]					
1.5	Ear protection (earplugs etc)					
1.6	Eye protection appropriate to task performed					
1.7	Induction tags/cards					
1.8	Dust masks					
1.9	Asbestos PPE					
1.10	Covid 19 PPE					
1.11	Luminous high visibility safety vests					
1.12	Any other: Contractor to specify: ...Raincoats PPE.....					
2.	Performing work in a Fall Risk Position					
2.1	Fall Protection Plan developer	Construction Regulation 10: Fall Protection				
2.2	Fall Protection Plan					
2.3	Fall protection equipment (Safety Harness)					
2.4	Fall Prevention equipment (Guardrails, barricading, anchors)					
2.5	Evaluation of physical fitness of personnel working at heights					
2.6	Any other: Contractor to specify:					
3	Barricading and Signage					
3.1	Supply & installation, including removal upon completion to ensure full compliance to legislation	Construction Regulation 13: Excavation				
3.2	Rigid type barricading					
3.3	Temporary fence barricading along perimeter of excavated area					
3.4	Appropriate equipment/tools for excavation.					
3.5	Provision of all signage for all relevant activities in terms of latest revision of legislation	General Safety Regulation 2B: Display of substituted notices and signs				
3.5	Any other: Contractor to specify:					
4	Related Training					
4.1	Induction Training					
4.2	First Aid Training					
4.3	Health and Safety Representative training					
4.4	Incident Investigator Training					

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	OHS SPECIFICATION Major and Minor Distribution projects, installation, replacement and refurbishment of Smart meters	Template Identifier	240-73416879	Rev	2
		Document Identifier	High/ Constr 1	Rev	1
		Effective Date	April 2023		
		Review Date	April 2026		

4.5	Hazard Identification & Risk Assessment Training	Construction Regulations, General Safety Regulations, ORHVS, Driven Machinery Regulations				
4.6	Training of Personnel working at heights					
4.7	Operating for High Voltage systems					
4.8	Ladder Inspector Training					
4.9	Crane Operator Training					
4.1	Construction vehicle & Mobile plant Operator e.g. trucks, drills bakkies etc					
4.11	Training to operate Jackhammer, etc					
4.12	Fire Fighting Training					
4.13	Any other: Contractor to specify:					
5	Safety Management System					
5.1	Implementation of Health and Safety Management System on site as detailed in OHS Plan and associated documentation	Construction Regulation 7: Duties of Principal Contractor and contractor, 32-726: SHE Commercial Process, PLCM				
5.2	Availability of Principal Contractor resources & systems. Provision of monthly audits to ensure compliance to Client and Legislative requirements. Submission of monthly statistical data and audit reports to Client					
5.3	Site close out and OHS file submission					

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

Annexure 12 – OHS Tender Evaluation Template

	Annexure C 4: OHS Tender Evaluation Template (Construction work)	Template Identifier	240-43921898	Rev	5
		Document Identifier	240-106084699	Rev	2
		Effective Date	May 2021		

1. Tenderer's / Supplier's name: Tender Ref number:

Scope of work:

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No N/A = Not applicable	
1	Annexure B		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No N/A = Not applicable	
	Is the acknowledgement of Eskom's OHS legal and other requirements form signed and submitted by the tenderer?		
2	OHS plan (Must address the project /scope of work OHS risk(s) and aligned with the health and safety specification or requirements)		
3	Costing for Health and Safety management Has the tenderer submitted detailed costing for OHS (the cost should be broken down not provided as a lump sum)? <ul style="list-style-type: none"> The costing must be based on the overall scope of work/service to be performed; 		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No N/A = Not applicable	
	<ul style="list-style-type: none"> The scope of work and the risk assessment may serve as a guideline. 		
4	Valid Letter of Good Standing (COIDA or equivalent)		
5	OHS policy signed by CEO The submitted policy document must comply to OHS Act Section 7		
6	OHS Competency (Consider scope of work, risks, OHS plan and applicability) Qualifications / competencies required) Submit proof of accreditation for training providers (SAQA/QCTO) - First aiders GSR 3(4)		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No N/A = Not applicable	
	<ul style="list-style-type: none"> - Fire fighters CR 29 (i) - Construction Supervisor CR 8(7) - Construction Manager CR 8(1) SACPMP registered. - Safety officer CR 8(5) (SACPCMP registered) - OHS Representative OHS sec 17 - HCA Controller - Incident investigator GAR 9(2) - Fall Protection Plan Developer CR 10(1)a - Truck Mounted Crane Operator CR 22(a) 		
7	Medical Fitness Certificates - by Occupational Health Practitioner for any two employees or Medical Program		
8	Fall protection plan CR 10		
9	Baseline Risk Assessment CR 9		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No N/A = Not applicable	
	Recommendation		Recommended or Not recommended.

*NOTE: For explanatory notes for the listed items (OHS requirements) please refer to [240 - 77433139 Annexure A: Supplier Risk Category](#)

1. Other requirements

Annotation: Populate additional OHS tender returnable(s) that are applicable to the scope of work and need to be evaluated prior to contract award. *This section must be deleted if not applicable.*

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

<u>Ref.</u>	<u>OHS Tender Returnable</u>	<u>Submission</u>	<u>Comments</u>
		Y = Yes N= No	
	Recommendation		Recommended /Not Recommended

.....

Eskom OHS Representative

.....

Designation

.....

Signature

.....

Date

Development Team

Diane Maunatlala

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.