

DETAILED SPECIFICATION:

To be captured on SBD 3.1

Item	Description	Quantity	Total Cost
1	11th floor – WSSS Office • Finish off the incomplete window installation in between the partitioned windows. • Install the locking mechanisms on the front sliding windows of the partitioned offices to make the windows lockable from inside. • Supply and install the wallpaper on the internal and external surfaces of the partitioned offices. • Apply the necessary finishing touches (i.e. aluminium skirting, corner protectors, etc.) to the partition dry walls. • The wallpaper must be properly installed and protected such that it does not peel off on its own.	6 x Offices and 1 photocopy room	